



**ENERGY, MINES AND
RESOURCES CANADA**

CANADA CENTRE FOR MINERAL AND
ENERGY TECHNOLOGY

NATIONAL URANIUM TAILINGS PROGRAM

**FINAL REPORT
FOR**

**COST STUDY ON WASTE MANAGEMENT
AT THREE MODEL CANADIAN
URANIUM MINES**

CAPITAL COSTS - ESTIMATE DETAILS

MARCH, 1984

KILBORN (SASKATCHEWAN) LTD.

MELIS CONSULTING ENGINEERS LTD.

REQ. NO. 3-1653

CONTRACT REPORT NO. OSG83-00232

COST STUDY ON WASTE MANAGEMENT
AT
THREE MODEL CANADIAN URANIUM MINES
CAPITAL COST ESTIMATE DETAILS

prepared for

DEPARTMENT OF ENERGY, MINES AND RESOURCES
CANADA CENTRE FOR MINERAL AND ENERGY TECHNOLOGY
NATIONAL URANIUM TAILINGS PROGRAM

by

KILBORN (SASKATCHEWAN) LTD.
and
MELIS CONSULTING ENGINEERS LTD.

JUL 30 1984

MICROMEDIA

108pp

March, 1984

Saskatoon, Canada

COST STUDY ON WASTE MANAGEMENT
AT
THREE MODEL CANADIAN URANIUM MINES
CAPITAL COST ESTIMATE DETAILS

- 1.0 Model A Capital Cost Estimate Details
- 2.0 Model B Capital Cost Estimate Details
- 3.0 Model C Capital Cost Estimate Details

1.0 MODEL A CAPITAL COST ESTIMATE DETAILS

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

PROJECT SUMMARY

RUN NO. P08

PAGE 1

RUN : 28 MAR 84
TIME: 12:40

AREA	DESCRIPTION	----- MHRS	LABOR ----- COST	H.O.	----- MATERIAL FIELD	----- TOTAL	TOTAL COST
321	MINE WATER TREATMENT	53,048	1,856,678	2,631,414	567,647	3,199,061	5,055,739
322	MILL EFFLUENT TREATMENT	82,612	2,891,419	3,993,221	1,182,202	5,175,423	8,066,842
323	LINESTONE CIRCUIT	1	22	-22	-22	0	0
324	LINE CIRCUIT	-0	-7	-1	8	8	0
32-		135,660	4,748,111	6,624,635	1,749,835	8,374,470	13,122,581*
331	TAILINGS LINE	2,777	97,178	474,600	142,633	617,233	714,411
332	TAILINGS STORAGE BASIN				5,721,494	5,721,494	5,721,494
333	TAILINGS DECANT TREATMENT	6,242	218,459	298,226	2,429,450	2,727,676	2,946,136
334	MONITORING	1,572	55,020	180,021	21,600	201,621	256,641
33-		10,590	370,657	952,847	8,315,177	9,268,024	9,638,681*
3--		146,251	5,118,768	7,577,482	10,065,012	17,642,494	22,761,262*
900	CONST. INDIRECTS, E.P.C.M. & CONTINGENCY	46,450	1,625,750	4,052,400	2,224,000	6,276,400	7,902,150
---		192,701	6,744,518	11,629,882	12,289,012	23,918,894	30,663,412*
	PROJECT TOTAL	192,701	6,744,518	11,629,882	12,289,012	23,918,894	30,663,412*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL A

AREA/CLASS MATRIX

RUN NO. P08

PAGE 1
RUN : 28 MAR 84
TIME: 12:42

AREA DESCRIPTION	SITENWORK & IMPROVEMENTS (.1---)	BUILDINGS (.2---)	EQUIPMENT GENERAL (.3---)	MECH PROCESS (.4---)	PROCESS PIPING (.5---)	ELECTRICAL POWER (.6---)	INSTRUMENTATION (.7---)	TRANSFERS (.8---)	AREA TOTAL
321 MINE WATER TREATMENT		2,333,664		1,378,407	275,680	275,670	137,855	654,463	5,055,739
322 MILL EFFLUENT TREATMENT		2,023,974		1,993,585	398,711	398,718	199,358	3,052,496	8,066,842
323 LIMESTONE CIRCUIT		1,518,480		1,626,588	325,322	325,303	162,663	-3,958,356	0
324 LIME CIRCUIT		1,780,218		796,407	159,260	159,265	79,645	-2,974,794	0
331 TAILINGS LINE	682,874						31,537		714,411
332 TAILINGS STORAGE BASIN	5,721,494								5,721,494
333 TAILINGS DECANT TREATMENT	2,304,288	255,003		158,114	31,720	121,695	15,815	59,501	2,946,136
334 MONITORING	31,645	89,996		135,000					256,641
TOTAL DIRECTS	8,740,301	8,001,334		6,088,100	1,190,693	1,280,651	626,873	-3,166,690	22,761,262

ESTIMATE DETAILS

RUN NO. P08

RUN : 28 MAR 84

TIME: 12:03

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.D. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINE WATER TREATMENT</u>														
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	23360	CM	1.14	26,630	35	932,064	60.00	1,401,600			1,401,600	2,333,664
4630	1	THICKENER U/F PUMP 150MM	1	LS						32,000			32,000	32,000
4630	2	LAUNDER - THICKENER U/F PUMP	1	LS						2,000			2,000	2,000
4630	5	MINEWATER SLUDGE PUMP 75MM. X 40MM	1	LS						3,500			3,500	3,500
4630	10	MINEWATER FLOCCULANT TRANSFER PUMP 50MM X 50MM	1	LS						2,950			2,950	2,950
4630	15	MINEWATER FLOCCULANT METERING PUMPS	2	EA					1,770.00	3,540			3,540	3,540
4630	16	FLOCCULANT FLOWMETER	1	LS						500			500	500
4640	1	SUMP PUMPS 50MM	2	EA					3,500.00	7,000			7,000	7,000
4650	1	MINEWATER PUMPS 150MM X 100MM	2	EA					3,860.00	7,720			7,720	7,720
										44,490			44,490	44,490*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 2

RUN : 28 MAR 84

TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
AREA 321 - MINE WATER TREATMENT													
4650	2	MOTORS 30HP	2	EA				1,300.00	2,600			2,600	2,600
4650	5	MINEWATER THICKENER D/F PUMPS-150MM. X 100MM	2	EA				3,860.00	7,720			7,720	7,720
4650	6	MOTOR - 40HP	2	EA				2,200.00	4,400			4,400	4,400
4650									22,440			22,440	22,440*
46--									73,930			73,930	73,930*
4820	1	MINEWATER STORAGE TANKS 15000MM DIA. X 20000MM (2 REQ'D)	151340	KG				2.80	423,752			423,752	423,752
4820	2	EPOXY LINING	151	TN	5.71	862	35		30,177	200.00	30,200	30,200	60,377
4820	5	PRECIPITATION TANKS 6000MM DIA. X 6000MM (2 REQ'D)	25730	KG				2.80	72,044			72,044	72,044
4820	6	AGITATORS	2	EA				27,370.00	54,740			54,740	54,740
4820	7	MOTORS-30HP	2	EA				1,300.00	2,600			2,600	2,600
4820	8	RUBBER LINING TANKS	292	SM	3.85	1,124	35		39,347	135.00	39,420	39,420	78,767

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 5

RUN : 28 MAR 84

TIME: 12:03

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	HH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 322 - MILL EFFLUENT TREATMENT													
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	20260	CM	1.14	23,096	35	808,374	60.00	1,215,600		1,215,600	2,023,974
4190	1	TAILINGS SAMPLER	1	LS						7,080		7,080	
4440	5	BRIDGE CRANE - TAILINGS NEUTRALIZATION AREA 2.5 TONNE	1	LS						77,500		77,500	
4610	1	AIR COMPRESSOR -2000CM/H 414KPA C/W 300HP MOTOR & FULL VOLTAGE STARTER	2	EA					67,780.00	135,560		135,560	
4630	1	TAILINGS PUMPS 300MM X 250MM	6	EA					14,660.00	87,960		87,960	
4630	2	MOTORS 175HP	6	EA					12,000.00	72,000		72,000	
4630	3	VARIASPEED MOTOR CONTROLS	2	EA					59,000.00	118,000		118,000	
4630	15	GLAND WATER PUMPS 75MM X 50MM	2	EA					2,540.00	5,080		5,080	
4630	16	MOTORS 40HP	2	EA					2,200.00	4,400		4,400	
4630										287,440		287,440	287,440*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 6

RUN : 28 MAR 84

TIME: 12:03

CLS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL	MHRS	RT	LABOR	TOTAL	UNIT	CS	--- H.O. MATERIAL ---	TOTAL	UNIT	CS	FIELD MATERIAL	TOTAL	MAT'L	TOTAL	COST
-----	-----	-------------	------	----	------	-------	------	----	-------	-------	------	----	-----------------------	-------	------	----	----------------	-------	-------	-------	------

AREA 322 - MILL EFFLUENT TREATMENT

4640	5	SUMP PUMP - TAILINGS NEUTRALIZATION AREA 75MM	1	LS										4,470					4,470		4,470
------	---	---	---	----	--	--	--	--	--	--	--	--	--	-------	--	--	--	--	-------	--	-------

4640	6	MOTOR 25 HP	1	LS										1,120					1,120		1,120
------	---	-------------	---	----	--	--	--	--	--	--	--	--	--	-------	--	--	--	--	-------	--	-------

4640														5,590					5,590		5,590*
------	--	--	--	--	--	--	--	--	--	--	--	--	--	-------	--	--	--	--	-------	--	--------

46--														428,590					428,590		428,590*
------	--	--	--	--	--	--	--	--	--	--	--	--	--	---------	--	--	--	--	---------	--	----------

4820	1	TAILINGS JUNCTION BOX	900	KG									4.70	4,230					4,230		4,230
------	---	-----------------------	-----	----	--	--	--	--	--	--	--	--	------	-------	--	--	--	--	-------	--	-------

4820	2	RUBBER LINING - JUNCTION BOX	18	SM									170.00	3,060					3,060		3,060
------	---	---------------------------------	----	----	--	--	--	--	--	--	--	--	--------	-------	--	--	--	--	-------	--	-------

4820	5	NEUTRALIZATION PACHUCA TANKS 10000MM DIA.X 20000MM (3-RED'D)	212050	KG									2.80	593,740					593,740		593,740
------	---	--	--------	----	--	--	--	--	--	--	--	--	------	---------	--	--	--	--	---------	--	---------

4820	6	RUBBER LINING	1734	SM	3.84	6,659	35		233,050								135.00	234,090		234,090
------	---	---------------	------	----	------	-------	----	--	---------	--	--	--	--	--	--	--	--------	---------	--	---------

4820						6,659			233,050					601,030				234,090		835,120
------	--	--	--	--	--	-------	--	--	---------	--	--	--	--	---------	--	--	--	---------	--	---------

4910	1	FIELD MATERIAL 10% OF H. O. MATERIAL	1	LS														111,420		111,420
------	---	---	---	----	--	--	--	--	--	--	--	--	--	--	--	--	--	---------	--	---------

4920	1	MECHANICAL INSTALLATION 27% OF H. O. MATERIAL	1	LS		8,595	35		300,825												300,825
------	---	--	---	----	--	-------	----	--	---------	--	--	--	--	--	--	--	--	--	--	--	---------

49--						8,595			300,825									111,420		111,420	412,245*
------	--	--	--	--	--	-------	--	--	---------	--	--	--	--	--	--	--	--	---------	--	---------	----------

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 7
RUN : 28 MAR 84
TIME: 12:03

CLSS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
4---						15,254		533,875		1,114,200		1,459,710	1,993,585*
5000	1	PROCESS PIPING 20% OF INSTALLED MECH	1	LS		6,835	35	239,225				159,486	398,711
6000	1	ELECTRICAL 20% OF INSTALLED MECH	1	LS		5,696	35	199,360				199,358	398,718
7000	1	INSTRUMENTATION 10% OF INSTALLED MECH	1	LS		1,424	35	49,840				149,518	199,358
8000	1	CREDIT FROM LIME CIRCUIT (AREA 324) OF 76%	1	LS		22,557	35	789,495		1,271,140		1,471,335	2,260,830
8000	2	CREDIT FROM LIMESTONE CIRCUIT (AREA 323) OF 20%	1	LS		7,750	35	271,250		392,281		520,416	791,666
8000						30,307		1,060,745		1,663,421		1,991,751	3,052,496*
AREA 322	TOTAL					82,612		2,891,419		3,993,221		5,175,423	8,066,842*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 8

RUN : 28 MAR 84

TIME: 12:03

CLS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	HH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	15200	CM	1.14	17,328	35	606,480	60.00	912,000		912,000	1,518,480
4100	1	LIMESTONE BALL MILL 2250MM DIA X 3500MM	1	LS						228,680		228,680	228,680
4100	2	MOTOR-300HP	1	LS						26,000		26,000	26,000
4100	3	CHUTE- DISCHARGE	1	LS						2,000		2,000	2,000
4100										256,680		256,680	256,680*
4180	1	LIMESTONE VIBRATING FEEDER	1	LS						4,130		4,130	4,130
4180	5	SLOT FEEDER 610MM	1	LS						7,115		7,115	7,115
4180										11,245		11,245	11,245*
41--										267,925		267,925	267,925*
4220	1	PRIMARY CYCLONE 400MM DIA.	1	LS						2,900		2,900	2,900
4220	5	SECONDARY CYCLONES 150MM DIA.	2	EA					1,800.00	3,600		3,600	3,600
4220										6,500		6,500	6,500*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 9

RUN : 28 MAR 84

TIME: 12:03

CLASS ITEM DESCRIPTION

UNIT

QUAN UN

TOTAL
MHHRS RT

TOTAL
LABOR

-- H.O. MATERIAL --
UNIT CST TOTAL

- FIELD MATERIAL -
UNIT CST TOTAL

TOTAL
MAT'L

TOTAL
COST

AREA 323 - LIMESTONE CIRCUIT

4410	1	LIMESTONE BIN FEED BELT CONVEYOR 915MM (55M C/C PULLEYS)	1	LS				66,550			66,550	66,550
------	---	--	---	----	--	--	--	--------	--	--	--------	--------

4410	2	MOTOR 20HP	1	LS				900			900	900
------	---	------------	---	----	--	--	--	-----	--	--	-----	-----

4410	3	DISCHARGE CHUTE	1	LS				2,000			2,000	2,000
------	---	-----------------	---	----	--	--	--	-------	--	--	-------	-------

4410	5	LIMESTONE BIN DISCHARGE BELT CONVEYOR 457MM (30M C/C PULLEYS)	1	LS				33,125			33,125	33,125
------	---	---	---	----	--	--	--	--------	--	--	--------	--------

4410	6	BELT SCALE	1	LS				17,900			17,900	17,900
------	---	------------	---	----	--	--	--	--------	--	--	--------	--------

4410	7	DISCHARGE CHUTE	1	LS				2,000			2,000	2,000
------	---	-----------------	---	----	--	--	--	-------	--	--	-------	-------

4410								122,475			122,475	122,475*
------	--	--	--	--	--	--	--	---------	--	--	---------	----------

4420	1		1	EA								0
------	---	--	---	----	--	--	--	--	--	--	--	---

4440	1	BRIDGE CRANE - LIMESTONE AREA - 10 TONNE	1	LS				119,600			119,600	119,600
------	---	---	---	----	--	--	--	---------	--	--	---------	---------

44--

4630	1	LIMESTONE SLURRY PUMPS 150MM X 100MM	2	EA				12,100.00			24,200	24,200
------	---	---	---	----	--	--	--	-----------	--	--	--------	--------

242,075

242,075*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

PAGE 10

RUN : 28 MAR 84

TIME: 12:03

RUN NO. P08

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 323 - Limestone CIRCUIT													
4630	2	MOTORS 30HP	2	EA					1,300.00	2,600		2,600	2,600
4630	5	PRIMARY CYCLONE FEED PUMP 100MM X 75MM	1	LS						12,100		12,100	12,100
4630	6	MOTOR 50 HP	1	LS						2,900		2,900	2,900
4630	10	SECONDARY CYCLONE FEED PUMP 100MM X 75MM	1	LS						8,575		8,575	8,575
4630	11	MOTOR 50HP	1	LS						2,900		2,900	2,900
4630	15	SECONDARY CYCLONE O/F PUMP 100MM X 75MM	1	LS						8,575		8,575	8,575
4630	16	MOTOR - 20HP	1	LS						900		900	900
4640	1	LIMESTONE AREA SUMP PUMP 50MM	2	EA					3,500.00	7,000		7,000	7,000
4640	5	TRUCK DUMP AREA SUMP PUMP 50MM	1	LS						3,500		3,500	3,500
4640										10,500		10,500	10,500*
46--										73,250		73,250	73,250*

KILBORN (SASKATCHEWAN) LTD.

ESTIMATE DETAILS

PAGE 11

 RUN : 28 MAR 84
 TIME: 12:03

PROJECT: S239-15

RUN NO. P08

NUTP WASTE MANAGEMENT COST STUDY MODEL A

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	-- FIELD MATERIAL -- UNT CST	TOTAL MAT'L	TOTAL COST
-------	------	-------------	------	----	------	----------------	----	----------------	--------------------------------	-------	---------------------------------	----------------	---------------

AREA 323 - LIMESTONE CIRCUIT

4810	1	LIMESTONE STORAGE BIN 350 TONNES	20480	KG					2.80	57,344		57,344	57,344
------	---	-------------------------------------	-------	----	--	--	--	--	------	--------	--	--------	--------

4810	2	TANK INSULATION	1	LS						14,125		14,125	14,125
------	---	-----------------	---	----	--	--	--	--	--	--------	--	--------	--------

4810	3	TANK STEAM HEATING COILS	1	LS						8,000		8,000	8,000
------	---	--------------------------	---	----	--	--	--	--	--	-------	--	-------	-------

4810										79,469		79,469	79,469*
------	--	--	--	--	--	--	--	--	--	--------	--	--------	---------

4820	10	LIMESTONE STORAGE TANKS 10000MM DIA. X 12000MM (2-REQD)	78780	KG					2.80	220,584		220,584	220,584
------	----	---	-------	----	--	--	--	--	------	---------	--	---------	---------

4820	11	RUBBER LINING	896	SM	3.84	3,441	35	120,422			135.00	120,960	241,382
------	----	---------------	-----	----	------	-------	----	---------	--	--	--------	---------	---------

4820	12	AGITATORS	2	EA					51,870.00	103,740		103,740	103,740
------	----	-----------	---	----	--	--	--	--	-----------	---------	--	---------	---------

4820	13	MOTORS 75HP	2	EA					4,300.00	8,600		8,600	8,600
------	----	-------------	---	----	--	--	--	--	----------	-------	--	-------	-------

4820	15	PRIMARY CYCLONE FEED PUMPBOX 1500MM DIA. X 2000MM	720	KG					4.70	3,384		3,384	3,384
------	----	---	-----	----	--	--	--	--	------	-------	--	-------	-------

4820	16	RUBBER LINING	14	SM					172.00	2,408		2,408	2,408
------	----	---------------	----	----	--	--	--	--	--------	-------	--	-------	-------

4820	20	SECONDARY CYCLONE FEED PUMPBOX 1250MM DIA. X 2000MM	555	KG					4.70	2,609		2,609	2,609
------	----	---	-----	----	--	--	--	--	------	-------	--	-------	-------

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. F08

PAGE 12
RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 323 - LIMESTONE CIRCUIT</u>														
4820	21	RUBBER LINING	11	SM					172.00	1,892			1,892	1,892
4820	25	SECONDARY CYCLONE O/F PUMPBOX 1250MM DIA X 2000MM	555	KG					4.70	2,609			2,609	2,609
4820	26	RUBBER LINING	11	SM					172.00	1,892			1,892	1,892
4820					3,441			120,422		347,717		120,960	468,677	589,099*
4840	1	LIMESTONE DUMP HOPPER C/W LINERS	4900	KG					4.70	23,030			23,030	23,030
4850	1	PRIMARY & SECONDARY U/F LAUNDER	1	LS						2,000			2,000	2,000
4850	2	RUBBER LINING	10	SM					172.00	1,720			1,720	1,720
4850	5	SECONDARY CYCLONE O/F LAUNDER	1	LS						2,000			2,000	2,000
4850	6	RUBBER LINING	5	SM					172.00	860			860	860
4850	10	PRIMARY CYCLONE O/F LAUNDER	1	LS						2,000			2,000	2,000
4850	11	RUBBER LINING	5	SM					172.00	860			860	860
4850										9,440			9,440	9,440*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

CLASS ITM DESCRIPTION

UNIT

MNRS

RT

TOTAL

LABOR

UNIT CST

- FIELD MATERIAL -

UNIT CST

TOTAL MAT'L

TOTAL COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 14

RUN : 28 MAR 84

TIME: 12:03

AREA 323 - LIMESTONE CIRCUIT

8000 2 CREDIT TO PRODUCTION
CAPITAL COST OF 80%

-1 LS

-31,000 35 -1,085,000

-1,569,125

-512,565

-2,081,690

-3,166,690

8000

-38,750

-1,356,250

-1,961,406

-640,700

-2,602,106

-3,958,356*

AREA 323 TOTAL

1

22

-22

-22

0*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 15
RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 324 - LIME CIRCUIT													
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	17820	CM	1.14	20,315	35	711,018	60.00	1,069,200		1,069,200	1,780,218
4100	5	LIME BALL MILL 1250MM DIA X 2000MM	1	LS						98,575		98,575	98,575
4100	6	MOTOR 100 HP	1	LS						5,500		5,500	5,500
4100	7	CHUTE-DISCHARGE	1	LS						2,000		2,000	2,000
4100													
4180	1	LIME SILO BIN ACTIVATOR	1	LS						106,075		106,075	106,075*
4180										19,000		19,000	19,000
41--													
4240	1	LIME SILO DUST COLLECTOR	1	LS						125,075		125,075	125,075*
4240										3,000		3,000	3,000

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 16

RUN : 28 MAR 84

TIME: 12:03

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	RT	TOTAL LAHOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
AREA 324 - LINE CIRCUIT															
4420	1	LINE SILO DISCHARGE SCREEN CONVEYOR	1	LS							13,800			13,800	13,800
4420	2	CHUTE-DISCHARGE	1	LS						2,000				2,000	2,000
4420											15,800			15,800	15,800*
4630	5	MILL DISCHARGE PUMPS 100MM X 75MM	2	EA					8,650.00		17,300			17,300	17,300
4630	6	MOTORS-25HP	2	EA					1,120.00		2,240			2,240	2,240
4630	10	LINE SLURRY DISCHARGE PUMPS 100MM X 75MM	2	EA					8,650.00		17,300			17,300	17,300
4630	11	MOTORS - 25HP	2	EA					1,120.00		2,240			2,240	2,240
4630											39,080			39,080	39,080*
4640	1	LINE AREA SUMP PUMP 50MM	1	LS							3,500			3,500	3,500
46--											42,580			42,580	42,580*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

CLASS ITEM DESCRIPTION

QUAN UN UNIT MTHRS

TOTAL MTHRS MH RT

TOTAL LABOR

-- H.O. MATERIAL --
UNT CST TOTAL

- FIELD MATERIAL -
UNT CST TOTAL

TOTAL MAT'L

TOTAL COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 18

RUN : 28 MAR 84

TIME: 12:03

AREA 324 - LINE CIRCUIT

4910	1	FIELD MATERIAL 10% OF H.O. MATERIAL	1	LS								60,335	60,335	60,335	
4920	1	MECHANICAL INSTALLATION 22% OF H.O. MATERIAL	1	LS	3,792	35	132,720					60,335	60,335	132,720	
49--					3,792		132,720					60,335	60,335	193,055*	
4---					3,792		132,720				603,352	663,687	796,407*		
5000	1	PROCESS PIPING 20% OF INSTALLED MECH.	1	LS	2,730	35	95,550					63,710	63,710	159,260	
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS	2,275	35	79,625					79,640	79,640	159,265	
7000	1	INSTRUMENTATION 10% OF INSTALLED MECH.	1	LS	569	35	19,915					59,730	59,730	79,645	
8000	1	CREDIT TO MINE EFFLUENT TREATMENT (AREA 322) OF 76%	-1	LS	-22,557	35	-789,495				-1,271,140	-200,195	-1,471,335	-2,260,830	
8000	2	CREDIT TO MINE WATER TREATMENT (AREA 321) OF 22%	-1	LS	-6,530	35	-228,550				-367,961	-57,952	-425,913	-654,463	

KILBURN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 19
RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	MHRS	TOTAL MHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
8000	3	CREDIT TO TAILINGS DECANT TREATMENT (AREA 333) OF 2%	-1	LS			-594	35		-20,790		-33,451		-5,260	-38,711	-59,501
8000							-29,681			-1,038,835		-1,672,552		-263,407	-1,935,959	-2,974,794*
AREA	324	TOTAL					-0			-7		-1		8	8	0*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

CLASS ITEM DESCRIPTION

QUAN UN MHR

TOTAL MHR RT

TOTAL LABOR

-- H.O. MATERIAL --
UNT CST TOTAL

-- FIELD MATERIAL --
UNT CST TOTAL

TOTAL MAT'L

TOTAL COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 20
RUN : 28 MAR 84
TIME: 12:03

AREA 331 - TAILINGS LINE

1800	1	TAILINGS LINES-SERIES	4200	M	.540	2,268	35	79,380	113.00	474,600	18.33	76,986	551,586	630,966
		160 400MM												
		(2 REQD)												

1900	1	EMERGENCY TAILINGS SPILL POND	2700	CM	.105	284	35	9,923	15.55	41,985	41,985	51,908
------	---	-------------------------------	------	----	------	-----	----	-------	-------	--------	--------	--------

1----

						2,552		89,303	474,600	118,971	593,571	682,874*
--	--	--	--	--	--	-------	--	--------	---------	---------	---------	----------

7000	1	INSTRUMENTATION - 5% OF TAILINGS LINE COST	1	LS		225	35	7,875		23,662	23,662	31,537
------	---	--	---	----	--	-----	----	-------	--	--------	--------	--------

AREA 331 TOTAL

						2,777		97,178	474,600	142,633	617,233	714,411*
--	--	--	--	--	--	-------	--	--------	---------	---------	---------	----------

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 21
RUN : 28 MAR 84
TIME: 12:03

CLSS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>														
1900	1	PERMANENT ROADWAYS FILL MATERIAL	198600	CM							6.50	1,290,900	1,290,900	1,290,900
1900	2	PERMANENT ROADWAYS COMPACTED GRANULAR FILL	8040	CM							7.30	58,692	58,692	58,692
1900	3	PERMANENT ROADWAYS CLEARING & GRUBBING	121900	HA							0.85	103,615	103,615	103,615
1900	50	MISC. SITE CLEARING & GRUBBING (BORROW PITS)	180000	SM							0.85	153,000	153,000	153,000
1900	51	MISC. SITE CLEARING TAILING POND	293	HA							3.600	1,054,800	1,054,800	1,054,800
1900	55	TEMPORARY ROADS - FILL	56400	CM							6.50	366,600	366,600	366,600
1900	56	TEMPORARY ROADS 150MM COMPACTED GRANULAR FILL	2820	CM							7.30	20,586	20,586	20,586
1900	57	TEMPORARY ROADS CLEARING & GRUBBING	37600	SM							0.85	31,960	31,960	31,960
1900	60	FRESH WATER DIVERSION DITCHES (EXCAVATED MATERIAL)	3616	CM							3.80	13,741	13,741	13,741
1900	65	DRAINING LAKE	1	LS								60,000	60,000	60,000

KILBORN (SASKATCHEWAN) LTD.

ESTIMATE DETAILS

PAGE 22
RUN : 28 MAR 84
TIME: 12:03

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

RUN NO. P08

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
AREA 332 - TAILINGS STORAGE BASIN														
1900	70	MOBILIZE & DEMOBILIZE	1	LS						185,000		185,000	185,000	
1900										3,338,894		3,338,894	3,338,894	
1910	5	DYKE NO.1 COMPACTED GRANULAR FILL	60	CM						7.30	438	438	438	
1910	6	DYKE NO.1 GRAVEL SHELL	212	CM						14.44	3,061	3,061	3,061	
1910	7	DYKE NO. 1 COARSE TILL	705	CM						7.16	5,048	5,048	5,048	
1910	8	DYKE NO. 1 LOW PERMEABILITY TILL CORE	1377	CM						9.00	12,393	12,393	12,393	
1910	9	DYKE NO.1 RIP RAP	212	CM						15.54	3,294	3,294	3,294	
1910	10	DYKE NO.1 SAND & GRAVEL FILTER	466	CM						15.71	7,321	7,321	7,321	
1910	11	DYKE NO.1 150MM DIA. DRAIN	23	M						14.50	334	334	334	

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 23

RUN : 28 MAR 84

TIME: 12:03

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>														
1910	12	DYKE NO.1 CENTRAL COLLECTION SUMP	1	LS						1,500		1,500	1,500	1,500
1910	13	DYKE NO.1 -GROUT CURTAIN INCL. GROUT HOLES,PRESS. GROUTING,SAND IN GROUT	1	LS						12,530		12,530	12,530	12,530
1910	14	DYKE NO.1 CLEAR & GRUBBING	1200	SH					0.85	1,020		1,020	1,020	1,020
1920	20	DYKE NO.2 150MM COMPACTED GRANULAR FILL	156	CM					7.30	1,139		1,139	1,139	1,139
1920	21	DYKE NO.2 GFAVEL SHELL	1663	CM					14.44	24,014		24,014	24,014	24,014
1920	22	DYKE NO.2 COARSE TILL	10720	CM					7.16	76,755		76,755	76,755	76,755
1920	23	DYKE NO.2 LOW PERMEABILITY TILL CORE	8715	CM					9.00	78,435		78,435	78,435	78,435
1920	24	DYKE NO.2 RIP RAP	1663	CM					15.54	25,843		25,843	25,843	25,843

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

PAGE 24

RUN : 28 MAR 84

TIME: 12:03

RUN NO. F08

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	-- FIELD MATERIAL -- UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>														
1920	25	DYKE NO.2 SAND & GRAVEL FILTER	4229	CM							15.71	66,438	66,438	66,438
1920	26	DYKE NO.2 150MM DIA. DRAIN	53	M							14.50	769	769	769
1920	27	DYKE NO.2 CENTRAL COLLECTION SUMP	1	LS						1,500		1,500	1,500	1,500
1920	28	DYKE NO.2 -GROUT CURTAIN INCL. GROUT HOLES,PRESS. GROUTING,SAND IN GROUT	1	LS						50,630		50,630	50,630	50,630
1920	29	DYKE NO.2 CLEARING & GRUBBING	5400	SM					0.85	4,590		4,590	4,590	4,590
1920	35	DYKE NO.3 150MM COMPACTED GRANULAR FILL	300	CM						330,112		330,112	330,112*	330,112*
1930	36	DYKE NO.3 GRAVEL SHELL	3719	CM					7.30	2,190		2,190	2,190	2,190
1930	37	DYKE NO.3 COARSE TILL	106140	CM					14.44	53,702		53,702	53,702	53,702
1930	37	DYKE NO.3 COARSE TILL	106140	CM					7.16	759,962		759,962	759,962	759,962

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 25

RUN : 28 MAR 84

TIME: 12:03

CLS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>														
1930	38	DYKE NO.3 UNSUITABLE EXCAVATION	52750	CM							3.80	200,450	200,450	200,450
1930	39	DYKE NO.3 LOW PERMEABILITY TILL CORE	38611	CM							9.00	347,499	347,499	347,499
1930	40	DYKE NO.3 RIP RAP	3719	CM							15.54	57,793	57,793	57,793
1930	41	DYKE NO.3 SAND & GRAVEL FILTER	12520	CM							15.71	196,689	196,689	196,689
1930	42	DYKE NO.3 150MM DIA. DRAIN	103	M							14.50	1,494	1,494	1,494
1930	43	DYKE NO.3 CENTRAL COLLECTION SUMP	1	LS								1,500	1,500	1,500
1930	44	DYKE NO.3 CONCRETE COLLAR	6	CM							450.00	3,600	3,600	3,600
1930	45	DYKE NO.3 450MM DIA. SCH.40 STEEL DECANT PIPES	540	M							300.00	162,000	162,000	162,000

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 26
RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHHRS	RM	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>															
1930	46	DYKE NO.3 -GROUT CURTAIN INCL.GROUT HOLES,PRESS. GROUT,SAND IN GROUT	1	LS							199,550		199,550	199,550	199,550
1930	47	DYKE NO.3 CONCRETE DECANT STRUCT.	1	LS							13,000		13,000	13,000	13,000
1930	48	DYKE NO.3 CLEARING & GRUBBING	7200	SM						0.85	6,120		6,120	6,120	6,120
1930											2,005,550		2,005,550	2,005,550	2,005,550
19--											5,721,494		5,721,494	5,721,494	5,721,494
AREA	332	TOTAL									5,721,494		5,721,494	5,721,494	5,721,494

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 27
RUN : 28 MAR 84
TIME: 12:03

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHHRS	HH RT	TOTAL LABOR	-- H.D. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 333 - TAILINGS DECANT TREATMENT</u>														
1940	1	SETTLING PONDS RIP RAP	6241	CM							15.54	96,985	96,985	96,985
1940	2	SETTLING PONDS 150MM COMPACTED GRANULAR FILL	6104	CM					7.30	44,559		44,559		44,559
1940	3	SETTLING PONDS 400MM DIA. SCH.40 STEEL PIPE C/W YELLOW JACKET	28	M					288.00	8,064		8,064		8,064
1940	4	SETTLING PONDS 300MM DIA. SCH.40 STEEL PIPE C/W YELLOW JACKET	62	M					187.00	11,594		11,594		11,594
1940	5	SETTLING PONDS FILTER MATERIAL	7607	CM					15.71	119,506		119,506		119,506
1940	6	SETTLING PONDS 100MM DIA.DRAIN	372	M					12.00	4,464		4,464		4,464
1940	7	SETTLING POND - "A" 30 MIL. HYPALON LINER	49055	SM					11.08	543,529		543,529		543,529
1940	8	SETTLING PONDS 150MM LINER SAND COVER	13384	CM					15.71	210,263		210,263		210,263

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 29

RUN : 28 MAR 84

TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	FIELD MATERIAL - UNT CST	TOTAL MATERIAL	TOTAL COST
-------	------	-------------	------	----	------	----------------	----------	----------------	--------------------------------	-----------------------------	-------------------	---------------

AREA 333 - TAILINGS DECANT TREATMENT

2000	2	DECANT TREATMENT BLDG. CONCRETE TANK LINING	604	SM	.114	69	35	2,410		12.42	7,502	9,912
2000						2,929		102,504		7,502	152,498	255,003*
4310	1	NEUTRALIZATION TANK AGITATOR	1	LS					144,996		18,920	18,920
4310	2	MOTOR 30HP	1	LS					1,300		1,300	1,300
4310	5	RADIUM PRECIPITATION TANK AGITATOR	1	LS					18,920		18,920	18,920
4310	6	MOTOR 30HP	1	LS					1,300		1,300	1,300
4310	10	SETTLING POND FLOCCULANT MIX TANK AGITATOR	1	LS					11,600		11,600	11,600
4310	11	MOTOR 30HP	1	LS					1,300		1,300	1,300
4310	12	FLOCCULANT MIX TANK ASPIRATOR	1	LS					200		200	200
4310									53,540		53,540	53,540*
4630	1	BARIUM CHLORIDE TRANSFER PUMP 100MM X 75MM	1	LS					2,890		2,890	2,890
4630	5	BARIUM CHLORIDE METERING PUMPS C/W MOTORS	2	EA				1,770.00			3,540	3,540

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 30

RUN : 28 MAR 84

TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD UNIT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 333 - TAILINGS DECANT TREATMENT</u>														
4630	10	SETTLING POND FLOCCULANT METERING PUMP	1	LS						1,770			1,770	1,770
4630	15	DECANT TREATMENT LINE PUMPS 40MM X 25MM	2	EA				5,690.00		11,380			11,380	11,380
4630										19,580			19,580*	19,580*
4640	1	DECANT TREATMENT AREA SUMP PUMP 50MM	1	LS						3,500			3,500	3,500
46--										23,080			23,080	23,080*
4820	10	BARIUM CHLORIDE MIX TANK 3000MM DIA X 3000MM	1829	KG					4.70	8,596			8,596	8,596
4820	11	FEED HOPPER	1	LS						2,000			2,000	2,000
4820	12	AGITATOR C/W MOTOR	1	LS						5,300			5,300	5,300
4820	13	EXHAUST FAN	1	LS						770			770	770
4820	15	BARIUM CHLORIDE STORAGE TANK 3000MM DIA. X 3000MM	1829	KG					4.70	8,596			8,596	8,596
4820	25	DECANT TREATMENT LINE TANK 3000MM DIA X 3000 MM	1829	KG					4.70	8,596			8,596	8,596

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUWP WASTE MANAGEMENT COST STUDY MODEL A

RUN NO. P08

ESTIMATE DETAILS

PAGE 31
RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
4820	26	AGITATOR	1	LS				9,300		9,300		9,300	9,300
4820										43,159		43,159*	43,159*
4910	1	FIELD MATERIAL 10% OF H. O. MATERIAL	1	LS						11,980		11,980	11,980
4920	1	MECHANICAL INSTALLATION 22% OF TOTAL MATERIAL	1	LS			753	35	26,355				26,355
49--							753		26,355			11,980	38,335*
4---							753		26,355	119,779		131,759	158,114*
5000	1	PROCESS PIPING 20% OF INSTALLED MECH	1	LS			542	35	18,970			12,750	31,720
6000	1	ELECTRICAL 20% OF INSTALLED MECH	1	LS			451	35	15,785			15,810	31,595
6000	2	ELECTRICAL - SUPPLY TO DECANT TREATMENT BLDG.	1	LS			860	35	30,100			60,000	90,100
6000							1,311		45,885			75,810	121,695*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

PAGE 32
RUN : 28 MAR 84
TIME: 12:03

RUN NO. F08

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 333 - TAILINGS DECANT TREATMENT</u>														
7000	1	INSTRUMENTATION 10% OF INSTALLED MECH	1	LS		113	35	3,955				11,860	11,860	15,815
8000	1	CREDIT FROM LINE CIRCUIT (AREA 324) OF 2%	1	LS		594	35	20,790		33,451		5,260	38,711	59,501
AREA	333	TOTAL				6,242		218,459		298,226		2,429,450	2,727,676	2,946,136*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

PAGE 33

RUN : 28 MAR 84

TIME: 12:03

CLSS ITM DESCRIPTION

QUAN UN

UNIT

TOTAL MH
MNHRS RTTOTAL
LABOR--- H.O. MATERIAL ---
UNT CST TOTAL- FIELD MATERIAL -
UNT CST TOTALTOTAL
MAT'LTOTAL
COST

AREA 334 - MONITORING

1900 1 DIKE PIEZOMETERS

1 LS

230

35

8,050

14,600

14,600

22,650

1900 2 SAMPLING WELLS

1 LS

57

35

1,995

7,000

7,000

8,995

1900

287

21,600

21,600

31,645*

2000 1 LABORATORY BLDG.

300 SM

14.28

4,284

35

149,940

500.00

150,000

150,000

150,000

299,940

2000 2 CREDIT TO PRODUCTION
CAPITAL COST-70%

-1 LS

-2,999

35

-104,965

-104,979

-104,979

-104,979

-209,944

2000

4000 1 LAB EQUIPMENT

1 LS

1,285

44,975

45,021

45,021

45,021

89,996*

4000 2 CREDIT TO PRODUCTION
CAPITAL COST - 70%

-1 LS

-315,000

-315,000

-315,000

-315,000

-315,000

4000

135,000

135,000

135,000

135,000*

AREA 334 TOTAL

1,572

55,020

180,021

21,600

201,621

256,641*

KILBORN (SASKATCHEWAN) LTD.

PAGE 34

RUN : 28 MAR 84

TIME: 12:03

ESTIMATE DETAILS

PROJECT: S239-15

RUN NO. F08

NUTP WASTE MANAGEMENT COST STUDY MODEL A

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	UNIT MHS	TOTAL MHS	RT	LABOR	UNIT CST	--- H.O. MATERIAL --- TOTAL	--- FIELD MATERIAL --- TOTAL	TOTAL MAT'L	TOTAL COST
AREA 900	-	CONST. INDIRECTS, E.P.C.M. & CONTINGENCY											
9100	1	CONSTRUCTION INDIRECTS	1	LS		23,700	35	829,500			991,500	991,500	1,821,000
9200	1	ENGINEERING, PROCUREMENT AND CONSTRUCTION MANAGEMENT	1	LS					2,731,000			2,731,000	2,731,000
9300	1	SPARE PARTS - 5% OF H.O. MATERIALS	1	LS					562,500			562,500	562,500
9900	1	CONTINGENCY	1	LS		22,750	35	796,250		758,900	1,232,500	1,991,400	2,787,650
9---						46,450		1,625,750		4,052,400	2,224,000	6,276,400	7,902,150*
AREA 900		TOTAL				46,450		1,625,750		4,052,400	2,224,000	6,276,400	7,902,150*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUFP WASTE MANAGEMENT COST STUDY MODEL A

ESTIMATE DETAILS

RUN NO. P08

RUN : 28 MAR 84
TIME: 12:03

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	UNIT MHRS	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
TOTAL	DIRECTS					192,701		6,744,518	11,629,882	11,629,882	12,289,012	12,289,012	23,918,894	30,663,412*
TOTAL	DIRECTS AND INDIRECTS					192,701		6,744,518	11,629,882	11,629,882	12,289,012	12,289,012	23,918,894	30,663,412*
CONTINGENCY														0*
PROJECT	TOTAL					192,701		6,744,518	11,629,882	11,629,882	12,289,012	12,289,012	23,918,894	30,663,412*

2.0 MODEL B CAPITAL COST ESTIMATE DETAILS

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL B

PROJECT SUMMARY

RUN NO. POB

PAGE 1

RUN : 28 MAR 84

TIME: 14:07

AREA	DESCRIPTION	MNRS	LABOR	H.O.	MATERIAL	TOTAL	TOTAL
			COST		FIELD	COST	
321	MINERWATER TREATMENT	139	6,950	14,660	244,365	259,025	265,975
322	MILL EFFLUENT TREATMENT	18,297	914,843	1,113,470	482,495	1,595,965	2,510,808
32-		18,436	921,793	1,128,130	726,860	1,854,990	2,776,783*
331	TAILINGS LINE	479	23,929	190,297	93,694	283,990	307,919
332	TAILINGS STORAGE BASIN	12,030	601,492	3,000,012	9,699,542	12,699,554	13,301,046
333	TAILINGS DECANT TREATMENT	16,810	840,500	765,693	781,780	1,547,473	2,387,973
334	MONITORING	1,080	54,000	193,000	35,400	228,400	282,400
33-		30,398	1,519,921	4,149,002	10,610,416	14,759,417	16,279,338*
3--		48,834	2,441,713	5,277,132	11,337,275	16,614,407	19,056,121*
900	CONST. INDIRECTS, E.P.C.M. & CONTINGENCY	29,125	1,456,250	3,128,820	1,803,130	4,931,950	6,388,200
---		77,959	3,897,963	8,405,952	13,140,405	21,546,357	25,444,321*
	PROJECT TOTAL	77,959	3,897,963	8,405,952	13,140,405	21,546,357	25,444,321*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

AREA/CLASS MATRIX

PAGE 1

RUN : 28 MAR 84

TIME: 14:09

RUN NO. P08

AREA DESCRIPTION	SITework & IMPROVEMENTS (.1----	BUILDINGS (.2----	EQUIPMENT GENERAL (.3----	MECH PROCESS (.4----	PROCESS PIPING (.5----	ELECTRICAL POWER (.6----	INSTRUMENTATION (.7----	TRANSFERS (.8----	AREA TOTAL
321 MINewater TREATMENT	240,795			20,980		4,200			265,975
322 MILL EFFLUENT TREATMENT		528,525		716,450	143,250	143,295	71,650	907,638	2,510,808
331 TAILINGS LINE	307,919								307,919
332 TAILINGS STORAGE BASIN	13,301,046								13,301,046
333 TAILINGS DECANT TREATMENT		901,100		991,293	198,250	198,230	99,100		2,387,973
334 MONITORING	57,400	90,000		135,000					282,400
TOTAL DIRECTS	13,907,160	1,519,625		1,863,723	341,500	345,725	170,750	907,638	19,056,121

KILBURN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 2

RUN : 28 MAR 84

TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MHHRS	MH RT	TOTAL LABOR	-- H.D. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINEWATER TREATMENT</u>													
1900	1	MINEWATER POND CUT MATERIAL	17300	CM						2.70	46,710	46,710	46,710
1900	2	MINEWATER POND TILL FILL	14600	CM						1.71	24,966	24,966	24,966
1900	3	MINEWATER POND COMPACTED GRANULAR FILL	386	CM						4.92	1,899	1,899	1,899
1900	4	MINEWATER POND RIP RAP	1400	CM						15.54	21,756	21,756	21,756
1900	5	MINEWATER POND SAND	1404	CM						2.20	3,089	3,089	3,089
1900	6	MINEWATER POND BOMIL SYN. LINER	7225	SM						17.16	123,981	123,981	123,981
1900	7	MINEWATER POND HIGH LEVEL ALARM	1	LS							1,500	1,500	1,500
1900	8	MINEWATER POND CONCRETE PAD	4	CM						450.00	1,800	1,800	1,800
1900	9	MINEWATER POND 150MM DIA. DRAIN	114	M						13.20	1,505	1,505	1,505
1900	10	MINEWATER POND EMERGENCY O/F PIPE (300MM DIA. STEEL)	20	M						60.00	1,200	1,200	1,200

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

PAGE 3

RUN : 28 MAR 84

TIME: 13:20

RUN NÚ. 008

[illegible]

KILBURN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 4

RUN : 28 MAR 84

TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
AREA 321 - MINERWATER TREATMENT														
6000	1	ELECTRICAL 20% OF INSTALLED MECH	1	LS		42	50	2,100				2,100	2,100	4,200
AREA 321 TOTAL														
						139		6,950		14,660		244,365	259,025	265,975*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 5
RUN : 28 MAR 84
TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	-- FIELD MATERIAL -- UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 322 - MILL EFFLUENT TREATMENT</u>												
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	3915	CM	1.35	5,285	50	67.50	264,263		264,263	528,525
4190	1	SLURRY SAMPLER-DISCHARGE NEUTRALIZATION TANK	1	LS					7,080		7,080	7,080
4440	1	2.5 TONNE HOIST (MANUAL)	1	LS					1,000		1,000	1,000
4610	1	AIR COMPRESSOR 1000CM/H 414KPA-150HP MOTOR	1	LS					44,675		44,675	44,675
4630	1	TAILINGS PUMPS (200MM X 150MM)	4	EA				5,500.00	22,000		22,000	22,000
4630	2	MOTORS - 75 HP	4	EA				4,300.00	17,200		17,200	17,200
4630	3	VARI-SPEED DRIVE	2	EA				41,300.00	82,600		82,600	82,600
4630									121,800		121,800	121,800*
4640	1	TAILINGS AREA SUMP PUMP 75MM	1	LS					4,470		4,470	4,470
4640	2	MOTOR - 25HP	1	LS					1,120		1,120	1,120
4640									5,590		5,590	5,590*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 6

RUN : 28 MAR 84

TIME: 13:20

CLS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 322 - MILL EFFLUENT TREATMENT													
4650	1	GLAND WATER PUMPS (150MM X 25MM)	2	EA				1,770.00		3,540		3,540	3,540
46--													
4820	1	NEUTRALIZATION TANK FEED JUNCTION BOX	225	KG				4.70		1,058		1,058	1,058
4820	2	RUBBER LINING/- JUNCTION BOX	4	SM				171.00		684		684	684
4820	5	NEUTRALIZATION TANKS (3-REQ'D) 8000MM DIA X 8000MM	23050	KG				2.80		64,540		64,540	64,540
4820	6	AGITATORS -RUBBER COVR'D	3	EA				38,330.00		114,990		114,990	114,990
4820	7	MOTORS - 60HP	3	EA				3,600.00		10,800		10,800	10,800
4820	8	RUBBER LINING - NEUTRAL- IZATION TANKS	740	SM	2.69	1,991	50	99,530			135.00	99,900	199,430
4820	10	PUMPBOXES - TAILINGS 2000MM SQ X 2000MM (2- REQ'D)	1960	KG				4.70		9,212		9,212	9,212
4820	11	RUBBER LINING - TAILINGS PUMPBOX	39	SM				172.60		6,731		6,731	6,731
4820						1,991		99,530		208,015		99,900	407,445*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 7

RUN : 28 MAR 84

TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	HH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 322 - MILL EFFLUENT TREATMENT</u>													
4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS						39,170	39,170	39,170	39,170
4920	1	MECHANICAL INSTALLATION 22% OF H.O. MATERIAL	1	LS	1,723	50	86,150						86,150
49--					1,723		86,150			39,170	39,170		125,320*
4---					3,714		185,680		391,700	139,070	530,770		716,450*
5000	1	PROCESS PIPING 20% OF INSTALLED MECH	1	LS	1,719	50	85,950			57,300	57,300		143,250
6000	1	ELECTRICAL 20% OF INSTALLED MECH	1	LS	1,433	50	71,650			71,645	71,645		143,295
7000	1	INSTRUMENTATION 10% OF INSTALLED MECH	1	LS	358	50	17,900			53,750	53,750		71,650
8000	1	CREDIT FROM LIME CIRCUIT (AREA 323) OF 67%	1	LS	5,788	50	289,400		457,508	160,730	618,238		907,638
AREA	322	TOTAL			18,277		914,843		1,113,470	482,495	1,595,965		2,510,808*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

CLASS ITEM DESCRIPTION

QUAN UNIT

TOTAL MH
MNHRS RT

TOTAL
LABOR

-- H.O. MATERIAL --
UNT CST TOTAL

- FIELD MATERIAL -
UNT CST TOTAL

TOTAL
MAT'L

TOTAL
COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 9

RUN : 28 MAR 84

TIME: 13:20

AREA 323 - LINE CIRCUIT

4240	1	DUST COLLECTOR - LINE SILO	1	LS						3,000			3,000		3,000
------	---	-------------------------------	---	----	--	--	--	--	--	-------	--	--	-------	--	-------

4420	1	SCREW CONVEYOR - LINE SILO DISCHARGE	1	LS						13,800			13,800		13,800
------	---	---	---	----	--	--	--	--	--	--------	--	--	--------	--	--------

4420	3	CHUTE - DISCHARGE	1	LS						2,000			2,000		2,000
------	---	-------------------	---	----	--	--	--	--	--	-------	--	--	-------	--	-------

4420										15,800			15,800		15,800*
------	--	--	--	--	--	--	--	--	--	--------	--	--	--------	--	---------

4440	1	2.5 TONNE HOIST (MANUAL)	1	LS						1,000			1,000		1,000
------	---	--------------------------	---	----	--	--	--	--	--	-------	--	--	-------	--	-------

44--										16,800			16,800		16,800*
------	--	--	--	--	--	--	--	--	--	--------	--	--	--------	--	---------

4630	5	LINE BALL MILL DISCHARGE PUMPS 50MM X 38MM	2	EA					6,200.00	12,400			12,400		12,400
------	---	---	---	----	--	--	--	--	----------	--------	--	--	--------	--	--------

4630	10	LINE SLURRY PUMPS (38MM X 25MM)	2	EA					5,690.00	11,380			11,380		11,380
------	----	------------------------------------	---	----	--	--	--	--	----------	--------	--	--	--------	--	--------

4630										23,780			23,780		23,780*
------	--	--	--	--	--	--	--	--	--	--------	--	--	--------	--	---------

4640	5	LINE MILL AREA SUMP PUMP 50MM	1	LS						3,600			3,600		3,600
------	---	----------------------------------	---	----	--	--	--	--	--	-------	--	--	-------	--	-------

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

WUP WASTE MANAGEMENT COST STUDY MODEL B

CLASS ITEM DESCRIPTION

QUAN UN UNIT

TOTAL MHRS

MH

RT

TOTAL LABOR

--- H.D. MATERIAL ---

UNT CST

--- FIELD MATERIAL ---

UNT CST

TOTAL MATERIAL

TOTAL

TOTAL MAT'L

TOTAL COST

ESTIMATE DETAILS

PAGE 11

RUN : 28 MAR 84

TIME: 13:20

RUN NO. P08

AREA 323 - LINE CIRCUIT

4920	1	MECHANICAL INSTALLATION	1	LS	1,620	50	81,000							81,000
		22% OF H.O. MATERIAL												

49--					1,620		81,000			36,800			36,800	117,800*
------	--	--	--	--	-------	--	--------	--	--	--------	--	--	--------	----------

4---					1,620		81,000		368,178	404,978			485,978*
------	--	--	--	--	-------	--	--------	--	---------	---------	--	--	----------

5000	1	PROCESS PIPING	1	LS	1,166	50	58,300			38,880			38,880	97,180
		20% OF INSTALLED MECH												

6000	1	ELECTRICAL	1	LS	972	50	48,600			48,600			48,600	97,200
		20% OF INSTALLED MECH												

7000	1	INSTRUMENTATION	1	LS	243	50	12,150			36,450			36,450	48,600
		10% OF INSTALLED MECH												

8000	1	CREDIT TO PRODUCTION	-1	LS	-4,470	50	-223,500		-223,545	-223,545			-447,045
		CAPITAL COST - 33%											

8000	2	CREDIT TO MILL EFFLUENT	-1	LS	-5,788	50	-289,400		-457,508	-618,238			-907,638
		TREATMENT (AREA 322) OF											
		67%											

8000					-10,258		-512,900		-681,053	-160,730			-1,354,683*
------	--	--	--	--	---------	--	----------	--	----------	----------	--	--	-------------

AREA 323 TOTAL				0		13		-13					0*
----------------	--	--	--	---	--	----	--	-----	--	--	--	--	----

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

PAGE 12
RUN : 28 MAR 84
TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST TOTAL	- FIELD UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 331 - TAILINGS LINE</u>													
1800	1	TAILINGS LINE TELEMETRY BUILDING	36	CM						100.00	3,600	3,600	3,600
1800	2	TAILINGS LINE 250MM DIA SERIES 160	4060	N	.113	459	50	22,939	42.61	5.76	23,366	196,382	219,321
1800	3	TAILINGS LINE FILL MATERIAL	12000	CM						4.40	52,800	52,800	52,800
1800	4	TAILINGS LINE CONTROL CABLE	1100	N	.018	20	50	990	13.00		14,300	14,300	15,290
1800						479		23,929	187,297	2.86	4,462	4,462	4,462
1900	1	EMERGENCY SPILL POND EXCAVATION SUITABLE MATERIAL	1560	CM								267,082	291,011*
1900	2	EMERGENCY SPILL POND TILL - BENTONITE	1	LS					3,000			3,000	3,000
1900	3	EMERGENCY SPILL POND FILL MATERIAL	1556	CM						4.40	6,846	6,846	6,846
1900	4	EMERGENCY SPILL POND COARSE TILL & ROCK	200	CM						13.00	2,600	2,600	2,600
1900													
1900													
---						479		23,929	190,297			16,908	16,908*
1900						479		23,929	190,297			283,990	307,919*
1900						479		23,929	190,297			283,990	307,919*
<u>AREA 331 TOTAL</u>													

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 13

RUN : 28 MAR 84

TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	HH RT	TOTAL LABOR	-- H.D. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>													
1900	1	PERMANENT ROADWAYS FILL MATERIAL	73200	CM						4.40	322,080	322,080	322,080
1900	2	PERMANENT ROADWAYS COMPACTED GRANULAR FILL	2900	CM						4.93	14,297	14,297	14,297
1900	3	PERMANENT ROADWAYS EXCAVATE UNSUITABLE MATERIAL	22800	CM						2.70	61,560	61,560	61,560
1900	5	MISC. CLEARING (BORROW AREAS)	1	LS	3,200	50	160,000		620,000		620,000		780,000
1900	10	STARTER DYKE EXCAVATE UNSUITABLE MATERIAL	1222000	CM						2.70	3,299,400	3,299,400	3,299,400
1900	11	STARTER DYKE TILL FILL	470940	CM						4.40	2,072,136	2,072,136	2,072,136
1900	12	STARTER DYKE RIP RAP	21580	CM						15.54	335,353	335,353	335,353
1900	13	STARTER DYKE COMPACTED GRANULAR SURFACE	2383	CM						4.92	11,724	11,724	11,724
1900	14	STARTER DYKE BENTONITE SEAL - POND BASE	9826	IN	.532	5,227	261,372	173.01	1,699,996	106.25	1,044,013	2,744,009	3,005,380

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

PAGE 14
RUN : 28 MAR 84
TIME: 13:20

RUN NO. P08

CLSS	ITH	DESCRIPTION	QUAN	UN	UNIT	MNRS	RT	TOTAL	HH	TOTAL	LABOR	UNT	H.O. MATERIAL	UNT	CST	TOTAL	- FIELD	UNT	CST	TOTAL	MAT'L	TOTAL	COST
AREA	332	- TAILINGS STORAGE BASIN																					
1900	15	STARTER DYKE	7505	TN	.480	3,602	50	180,120					173.22			1,300,016	95.80			718,979		2,018,995	2,199,115
		BENTONITE SEAL - EMBANKMENT																					
1900	20	MOBILIZE & DEMOBILIZE	1	LS																			
1900						12,030		601,492					3,000,012			3,000,012				9,699,542		12,699,554	13,301,046*
AREA	332	TOTAL				12,030		601,492					3,000,012			3,000,012				9,699,542		12,699,554	13,301,046*

KILBORN (SASKATCHEWAN) LTD.

ESTIMATE DETAILS

PAGE 15

RUN : 28 MAR 84

TIME: 13:20

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

RUN NO. 408

[illegible]

AREA 333 - TAILINGS DECANT TREATMENT

[illegible]

2000	2	DECANT LINE	500 M	58	50	2,900	7,600	5.80	2,900	10,500	13,400
2000	2	DECANT LINE	500 M	58	50	2,900	7,600	5.80	2,900	10,500	13,400

2000	3	SLUDGE RETURN LINE	600	M	50	3,000	11.83	7,100	5.00	3,000	10,100	13,100
2000	3	SLUDGE RETURN LINE	600	M	50	3,000	11.83	7,100	5.00	3,000	10,100	13,100

2000	4	POWER LINE & ELECTRICAL SUBSTATION	1	LS	432	50	21,600	43,000	64,600
2000	4	POWER LINE & ELECTRICAL SUBSTATION	1	LS	432	50	21,600	43,000	64,600

2000	8,650	432,500	14,700	453,900	468,600	901,100*
------	-------	---------	--------	---------	---------	----------

1170	1	SAND FILTERS C/W AUTO	1	15	224,200	224,200
------	---	-----------------------	---	----	---------	---------

4310	1	IN-LINE MINER-NITRIC ACID	1	LS	1,800	1,800
4310	1	IN-LINE MINER-NITRIC ACID	1	LS	1,800	1,800

4610	1	AIR COMPRESSOR 200 CM/H C/W TANK MOUNTED 25HP MOTOR	1	LS	7,375	7,375
------	---	---	---	----	-------	-------

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 16

RUN : 28 MAR 84

TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MATERIAL	TOTAL COST
AREA 333 - TAILINGS DECANT TREATMENT												
4620	1	FAN - BARIUM CHLORIDE MIX TANK VENT	1	LS					770		770	770
4630	1	SAND FILTER FEED PUMPS (150MM X 100MM)	2	EA				3,860.00	7,720		7,720	7,720
4630	2	MOTOR - 30HP	2	EA				1,300.00	2,600		2,600	2,600
4630	5	BACKWASH SURGE PUMPS (100MM X 75MM)	2	EA				6,460.00	12,920		12,920	12,920
4630	6	MOTORS - 30HP	2	EA				1,300.00	2,600		2,600	2,600
4630	10	BACKWASH PUMPS (100MM X 75MM)	2	EA				2,890.00	5,780		5,780	5,780
4630	11	MOTORS - 30HP	2	EA				1,300.00	2,600		2,600	2,600
4630	15	BARIUM CHLORIDE METERING PUMPS (13MM X 13MM)	2	EA				1,770.00	3,540		3,540	3,540
4630	20	BARIUM CHLORIDE TRANSFER PUMP (100MM X 75MM)	1	LS					2,585		2,585	2,585
4630	25	NITRIC ACID TRANSFER PUMP (75MM X 38MM)	1	LS					3,525		3,525	3,525

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 17
RUN : 28 MAR 84
TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 333 - TAILINGS DECANT TREATMENT</u>											
4630	30	NITRIC ACID FEED PUMP (100MM X 75MM)	1	LS				4,545		4,545	4,545
4630	31	MOTOR - 25HP	1	LS							
4630	35	FLOCCULANT METERING PUMP 13MM X 13MM	2	EA			1,120			1,120	1,120
							3,540			3,540	3,540
4630								53,075		53,075	53,075*
4640	1	DECANT AREA SUMP PUMP 50MM	1	LS			3,500			3,500	3,500
4640	5	NITRIC ACID AREA SUMP PUMP-50MM STAINLESS STL.	1	LS			5,700			5,700	5,700
4640	10	TAILINGS POND BARGE PUMPS 150MM C/W FLOATS & BLDG	1	LS			175,000			175,000	175,000
4640								184,200		184,200	184,200*
46--								245,420		245,420	245,420*
4820	1	DECANT TREATMENT TANKS 5000MM DIA. X 5000MM (2 REQ'D)	16340	KG			2.80	45,752		45,752	45,752

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 18
RUN : 28 MAR 84
TIME: 13:20

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT MHRS	TOTAL MHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 333 - TAILINGS DECANT TREATMENT</u>													
4820	2	AGITATOR (TANK #1 ONLY)	1	LS						18,540		18,540	18,540
4820	3	MOTOR - 25HP	1	LS						1,120		1,120	1,120
4820	5	PUMPOX - SAND FILTER FEED	780	KG					4.70	3,666		3,666	3,666
4820	10	BACKWASH SURGE TANK (6000MM DIA X 6000MM)	10930	KG					2.80	30,604		30,604	30,604
4820	15	BACKWASH TANK (6000MM DIA X 6000MM)	10930	KG					2.80	30,604		30,604	30,604
4820	20	BARIUM CHLORIDE MIX TANK (2500MM DIA X 2500MM)	1160	KG					4.70	5,452		5,452	5,452
4820	21	HOPPER - FEED	1	LS						2,000		2,000	2,000
4820	22	MIXER	1	LS						5,300		5,300	5,300
4820	25	BARIUM CHLORIDE STORAGE TANK (2500MM DIA X 2500MM)	1160	KG					4.70	5,452		5,452	5,452
4820	30	NITRIC ACID HOLDING TANK (STAINLESS STEEL) (4000MM DIA 4000MM)	5435	KG					5.77	31,360		31,360	31,360
4820	35	NITRIC ACID DILUTION TANK (STAINLESS STEEL) (6500MM DIA X 6500MM)	14140	KG					5.77	81,588		81,588	81,588

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

PAGE 19

RUN : 28 MAR 84

TIME: 13:20

RUN NO. P08

CLS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL	MN	RT	LABOR	UNT	H.O. MATERIAL	UNT	CS	FIELD MATERIAL	UNT	CS	TOTAL	MAT'L	TOTAL	COST
4820	40	FLOCCULANT MIX TANK (3000MM DIA X 3000MM)	1850	KG							4.70			8,695			8,695	8,695	8,695	
4820	41	AGITATOR	1	LS										8,420			8,420	8,420	8,420	
4820	42	MOTOR - 15HP	1	LS										820			820	820	820	
4820	43	ASPIRATOR	1	LS										200			200	200	200	
4820														279,573			279,573	279,573	279,573	
4910	1	FIELD MATERIAL 10% OF H.O.MATERIAL	1	LS										75,100			75,100	75,100	75,100	
4920	1	MECHANICAL INSTALLATION 22% OF H.O.MATERIAL	1	LS					165,200										165,200	
49--									3,304					75,100			75,100	75,100	240,300*	
4---									3,304					75,100			75,100	826,093	991,293*	
5000	1	PROCESS PIPING 20% OF INSTALLED MECH	1	LS					118,950					79,300			79,300	79,300	198,250	
6000	1	ELECTRICAL 20% OF INSTALLED MECH	1	LS					99,100					99,130			99,130	99,130	198,230	

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

PAGE 20
RUN : 28 MAR 84
TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
7000	1	INSTUMENTATION 10% OF INSTALLED MECH	1	LS		495	50	24,750				74,350	74,350	99,100
AREA	333	TOTAL				16,810		840,500		765,693		781,760	1,547,473	2,387,973*

KILGORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 21

RUN : 28 MAR 84

TIME: 13:20

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL	MH	RT	TOTAL	LABOR	UNT CST	MATERIAL --	UNT CST	TOTAL	FIELD MATERIAL -	UNT CST	TOTAL	MAT'L	TOTAL	COST
AREA 334 - MONITORING																				
1900	1	PIEZOMETERS	1	LS		140	50		7,000			13,000			27,400			40,400		47,400
1900	2	SAMPLING WELLS	1	LS		40	50		2,000						8,000			8,000		10,000
1900						180			9,000			13,000			35,400			48,400		57,400*
2000	1	LABORATORY BUILDING	300	SM	10	3,000	50		150,000	500.00		150,000						150,000		300,000
2000	2	CREDIT TO PRODUCTION CAPITAL COST - 70%	-1	LS		-2,100	50		-105,000			-105,000						-105,000		-210,000
2000						900			45,000			45,000						45,000		90,000*
4000	1	LAB. EQUIPMENT	1	LS								450,000						450,000		450,000
4000	2	CREDIT TO PRODUCTION CAPITAL COST - 70%	-1	LS								-315,000						-315,000		-315,000
4000												135,000						135,000		135,000*
AREA 334 TOTAL																				
						1,080			54,000			193,000			35,400			228,400		282,400*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

PAGE 22
RUN : 28 MAR 84
TIME: 13:20

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 900 - CONST. INDIRECTS, E.P.C.M. & CONTINGENCY</u>													
9100	1	CONSTRUCTION INDIRECTS	1	LS		15,245	50	762,250			762,230	762,230	1,524,480
9200	1	ENGINEERING, PROCUREMENT AND CONSTRUCTION MANAGEMENT	1	LS					2,286,740			2,286,740	2,286,740
9300	1	SPARE PARTS - 5% OF H.O. MATERIAL	1	LS					263,860			263,860	263,860
9900	1	CONTINGENCY	1	LS		13,880	50	694,000		578,220	1,040,900	1,619,120	2,313,120
9----						29,125		1,456,250		3,128,820	1,803,130	4,931,950	6,388,200*
AREA 900	TOTAL					29,125		1,456,250		3,128,820	1,803,130	4,931,950	6,388,200*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL B

ESTIMATE DETAILS

RUN NO. P08

RUN : 28 MAR 84
TIME: 13:20

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	HH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
TOTAL	DIRECTS					77,960		3,897,976	8,405,939	8,405,939	13,140,405	21,546,345	25,444,320*
TOTAL	DIRECTS AND INDIRECTS					77,960		3,897,976	8,405,939	8,405,939	13,140,405	21,546,345	25,444,320*
CONTINGENCY													0*
PROJECT	TOTAL					77,960		3,897,976	8,405,939	8,405,939	13,140,405	21,546,345	25,444,320*

3.0 MODEL C CAPITAL COST ESTIMATE DETAILS

KILBORN (SASATCHENAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

PROJECT SUMMARY

RUN NO. FOR

PAGE 1

RUN : 30 MAR 84

TIME: 14:45

AREA	DESCRIPTION	MINHRS	LABOR COST	H.O.	MATERIAL FIELD	TOTAL	TOTAL COST
321	MINEWATER TREATMENT	23,099	1,154,955	1,410,045	1,025,107	2,435,152	3,590,107
322	MILL EFFLUENT TREATMENT	127,020	6,350,999	7,882,299	2,808,183	10,690,482	17,041,481
323	LINE CIRCUIT			-0		-0	-0
324	BARIUM CHLORIDE			0		0	0
325	FLOCCULANT			0		0	0
326	NITRIC ACID			-0		-0	-0
32-		150,119	7,505,954	9,292,345	3,833,290	13,125,635	20,631,589*
331	TAILINGS LINE	9,071	453,565	854,400	410,576	1,264,976	1,718,541
332	TAILINGS STORAGE BASIN	10,660	533,010		11,404,592	11,404,592	11,937,602
334	MONITORING	2,783	139,150	216,180	857,595	1,073,775	1,212,925
33-		22,514	1,125,725	1,070,580	12,672,763	13,743,343	14,869,068*
3--		172,634	8,631,679	10,362,925	16,506,053	26,868,978	35,500,657*
900	CONST. INDIRECTS, E.F.C.M., & CONTINGENCY	48,503	2,425,150	6,526,670	3,212,715	9,739,385	12,164,535
---		221,137	11,056,829	16,889,595	19,718,768	36,608,363	47,665,192*
	PROJECT TOTAL	221,137	11,056,829	16,889,595	19,718,768	36,608,363	47,665,192*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

AREA/CLASS MATRIX

RUN NO. P08

PAGE 1

RUN : 30 MAR 84

TIME: 14:47

AREA DESCRIPTION	SITENETWORK & IMPROVEMENTS (.1---)	BUILDINGS (.2---)	EQUIPMENT GENERAL (.3---)	MECH PROCESS (.4---)	PROCESS PIPING (.5---)	ELECTRICAL POWER (.6---)	INSTRUMENTATION (.7---)	TRANSFERS (.8---)	AREA TOTAL
321 MINERWATER TREATMENT	656,755	1,050,000		839,038	167,800	167,800	100,710	602,004	3,590,107
322 MILL EFFLUENT TREATMENT		4,329,100		6,585,568	1,317,100	1,317,100	790,270	2,702,343	17,041,481
323 LIME CIRCUIT		843,700		747,714	149,550	149,550	89,725	-1,980,239	-0
324 BARIUM CHLORIDE		281,800		48,872	9,775	9,775	5,865	-356,087	0
325 FLOCCULANT		241,500		57,483	11,500	11,500	6,900	-328,893	0
326 NITRIC ACID		386,700		170,038	34,000	34,000	20,400	-645,138	-0
331 TAILINGS LINE	1,636,741						81,800		1,718,541
332 TAILINGS STORAGE BASIN	11,937,602								11,937,602
334 MONITORING	779,495	90,000		225,930	45,200	45,200	27,100		1,212,925
TOTAL DIRECTS	15,010,593	7,222,800		8,674,644	1,734,925	1,734,925	1,122,770	-0	35,500,657

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTF WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 1
RUN : 30 MAR 84
TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINERWATER TREATMENT</u>													
1900	1	MINERWATER & SETTLING PONDS - CUT MATERIAL	48330	CM						2.70	130,491	130,491	130,491
1900	2	MINERWATER & SETTLING PONDS - FILL & PLACEMENT MATERIAL	46750	CM						1.70	79,475	79,475	79,475
1900	3	MINERWATER & SETTLING PONDS - CLEARING	2	HA							32,750	32,750	32,750
1900	4	MINERWATER & SETTLING PONDS SAND FILTER BLANKET	2790	CM						2.20	6,138	6,138	6,138
1900	5	MINERWATER & SETTLING PONDS - TILL BENTONITE SEAL	32	TN						338.89	10,844	10,844	10,844
1900	6	MINERWATER & SETTLING PONDS -100 MIL SYNTHETIC LINER	8550	SM						20.63	176,387	176,387	176,387
1900	7	MINERWATER & SETTLING PONDS DRAINAGE PIPES	396	M						8.51	3,370	3,370	3,370
1900	8	MINERWATER & SETTLING PONDS - MISC. CARBON STEEL PIPE	1	LS							150,000	150,000	150,000

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 2

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINERWATER TREATMENT</u>												
1900	9	MINERWATER & PRECIP. PONDS MISC. CONC. VALVE HOUSE, SUMPS, & INSTRUMENTATION	1	LS								
									67,300		67,300	67,300
1900									656,755		656,755	656,755*
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	10500	CM	1	10,500	50	50.00	525,000		525,000	1,050,000
4130	1	SAND FILTERS (3 REQ'D) 2500MM DIA. X 3700MM) C/W CONTROLS & MEDIA	1	LS					168,150		168,150	168,150
4240	2	DUST COLLECTOR (FERRI-FLOC STORAGE BIN)	1	LS					3,000		3,000	3,000
4420	10	SCREW CONVEYOR - FERRI- FLOC STORAGE BIN DISCH. 150MM DIA X 7M LONG	1	LS					7,450		7,450	7,450
4440	1	2.5 TONNE HOIST (MANUAL)	1	LS					1,000		1,000	1,000
44--									8,450		8,450	8,450*
4630	1	SAND FILTER FEED PUMPS 150MM X 100MM	2	EA				3,860.00	7,720		7,720	7,720

KILBORN (SASATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

FABE 3
RUN : 30 MAR 84
TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINERWATER TREATMENT</u>											
4630	2	MOTORS - 25HP	2	EA				1,120.00		2,240	2,240
4630	5	BACKWASH PUMPS 100MM X 75MM	2	EA				2,585.00		5,170	5,170
4630	6	MOTOR - 15HP	2	EA				820.00		1,640	1,640
4630	10	FERRI-FLOC TRANSFER PUMP 100MM X 75MM	1	LS				4,540		4,540	4,540
4630	15	FERRI-FLOC METERING PUMP 38MM X 38MM	2	EA				3,000.00		6,000	6,000
4630										27,310	27,310*
4640	1	MINERWATER POND SUMP PUMPS 150MM	2	EA				5,135.00		10,270	10,270
4640	2	MOTORS - 40HP	2	EA				5,500.00		11,000	11,000
4640	5	MINERWATER TREATMENT AREA SUMP PUMP 50MM	1	LS				3,775		3,775	3,775
4640	10	SETTLING FOND NO.1 SUMP PUMP 100MM	2	EA				4,520.00		9,040	9,040
4640	11	MOTOR - 20HP	2	EA				900.00		1,800	1,800

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 4

RUN : 30 MAR 84

TIME: 14:51

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	MATERIAL TOTAL	TOTAL COST
<u>AREA 321 - MINERWATER TREATMENT</u>													
4640	15	SETTLING POND NO.2 SUMP PUMP - 100MM	2	EA				4,520.00		9,040		9,040	9,040
4640	16	MOTOR - 20HP	2	EA				900.00		1,800		1,800	1,800
4640	20	SITE RUNOFF SUMP PUMP 50MM	2	EA				3,775.00		7,550		7,550	7,550
4640	25	REAGENT AREA SUMP PUMP 50MM	1	LS						3,775		3,775	3,775
4640													
46--													
4810	5	STORAGE BIN (FERRI-FLOC) 600 TONNE 6000MM DIA X 8000MM	9220	KG						58,050		58,050	58,050*
										85,360		85,360	85,360*
								2.80		25,816		25,816	25,816
4810	6	DISCHARGE CHUTE - FERRI- FLOC STORAGE BIN	1	LS						2,000		2,000	2,000
4810													
4820	1	TREATMENT TANKS-NO.1 & 2 4500MM DIA X 4500MM (2 REQ'D)	14390	KG						27,816		27,816	27,816*
								2.80		40,264		40,264	40,264

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 5

RUN : 30 MAR 84

TIME: 14:51

CLS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHR	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
AREA 321 - MINERWATER TREATMENT													
4820	2	AGITATOR	2	EA				15,715.00		31,430		31,430	31,430
4820	3	MOTOR - 20HP	2	EA				900.00		1,800		1,800	1,800
4820	5	FLASH MIX TANK 1500MM DIA X 1500MM	620	KG				4.70		2,914		2,914	2,914
4820	6	AGITATOR	1	LS						6,725		6,725	6,725
4820	10	TREATMENT TANKS-NO. 3 & 4 (2 REQ'D) 4500MM X 4500MM	14380	KG				2.80		40,264		40,264	40,264
4820	11	AGITATOR	2	EA				15,715.00		31,430		31,430	31,430
4820	12	MOTOR - 20HP	2	EA				900.00		1,800		1,800	1,800
4820	15	FLASH MIX TANK 1500MM DIA X 1500MM	620	KG				4.70		2,914		2,914	2,914
4820	16	AGITATOR	1	LS						6,725		6,725	6,725
4820	20	SAND FILTER FEED PUMP 60X - 2000MM DIA. X 25"MM	925	KG				4.70		4,348		4,348	4,348
4820	25	PH ADJUSTMENT TANK 4500MM DIA. X 4500MM	7190	KG				2.80		20,132		20,132	20,132

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

WUP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 6

RUN : 30 MAR 84

TIME: 14:51

CLS5	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - RINSEWATER TREATMENT</u>														
4820	30	BACKWASH TANK 4500MM DIA. X 4500MM	7190	KG						2.80	20,132		20,132	20,132
4820	35	FERRI-FLOC MIXING TANK 3000MM DIA X 3000MM	2396	KG						4.70	11,261		11,261	11,261
4820	36	AGITATOR - RUBBER COVR'D	1	LS							11,700		11,700	11,700
4820	37	MOTOR - 15HP	1	LS							820		820	820
4820	38	RUBBER LINING - FERRI- FLOC MIXING TANK	145	SM	2.70	392	50		19,575			135.00	19,575	39,150
4820	40	FERRI-FLOC HOLDING TANK 5500MM DIA. X 5500MM	6653	KG						2.60	24,788		24,788	24,788
4820	41	AGITATOR - RUBBER COVR'D	1	LS							28,500		28,500	28,500
4820	42	MOTOR - 25HP	1	LS							1,120		1,120	1,120

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUP WASTE MANAGEMENT COST STUDY MODEL C

CLASS ITEM DESCRIPTION

QUAN UN UNIT MURS

TOTAL MH MURS RT

TOTAL LABOK

-- H.O. MATERIAL --
UNT CST TOTAL

- FIELD MATERIAL -
UNT CST TOTAL

TOTAL MAT'L

TOTAL COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 7
RUN : 30 MAR 84
TIME: 14:51

AREA 321 - WINEWATER TREATMENT

4820 43 RUBBER LINING - FERRI-
FLOC HOLDING TANK

31,860

4820

360,077*

48--

387,893*

4910 1 FIELD MATERIAL 10% OF
H.O. MATERIAL

58,185

4920 1 MECHANICAL INSTALLATION
22% OF H.O. MATERIAL

128,000

49--

186,185*

4---

839,038*

5000 1 PROCESS PIPING
20% OF INSTALLED MECH.

167,800

6000 1 ELECTRICAL
20% OF INSTALLED MECH.

167,800

7000 1 INSTRUMENTATION
12% OF INSTALLED MECH.

100,710

KILBORN (SASATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 8

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUANTITY	UNIT	TOTAL HOURS	MM RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 321 - MINERWATER TREATMENT</u>												
8000	1	CREDIT FROM LIME CIRCUIT AREA (323) OF 2.3%	1	LS	348	50	17,400		22,256		28,153	45,553
8000	2	CREDIT FROM BARIUM CHLORIDE AREA (324) OF 35.7%	1	LS	1,151	50	57,550		63,518		69,557	127,107
8000	3	CREDIT FROM FLOCCULANT AREA (325) OF 34.3%	1	LS	992	50	49,600		56,349		63,175	112,775
8000	4	CREDIT FROM NITRIC ACID AREA (326) OF 50.0%	1	LS	2,642	50	132,100		161,079		190,469	322,569
8000					5,133		256,650		303,202		351,354	608,004*
AREA	321	TOTAL			23,099		1,154,955		1,410,045		2,435,152	3,590,107*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTF WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 9

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	HH	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 322 - MILL EFFLUENT TREATMENT</u>													
2000	1	BUILDING - INCL. AMMONIUM SULPH. PLANT BLDG. & EQUIP SUPPORTS-BLDG. SERVICES	43291	CM	1	43,291	50	2,164,550	50.00	2,164,550		2,164,550	4,329,100
4130	1	DRUM FILTER C/W SCRAPER DISCHARGE, RUBBER COVERED, MILD STEEL	2	EA					236,000	472,000		472,000	472,000
4130	2	FILTRATE RECEIVER 760MM DIA. X 1530MM	2	EA					6,500.00	13,000		13,000	13,000
4130	3	SEAL TANKS 1000MM DIA. X 1000MM	3	EA					5,200.00	15,600		15,600	15,600
4130	4	CONDENSER 760MM DIA X 1530MM	1	LS						6,500		6,500	6,500
4130	5	REFULPER - DRUM FILTER DISCHARGE (1 REQ'D)	1	LS						11,300		11,300	11,300
4130	10	SAND FILTER - 2500MM X 3700MM (3 REQ'D) C/W CONTROLS & MEDIA	1	LS						168,150		168,150	168,150
4130										686,550		686,550	686,550*
4230	1	AMMONIUM SULPHATE PACK- AGE CRYSTALLIZATION/ DRYER PLANT (0.8T/H CAP)	1	LS						1,200,000		1,200,000	1,200,000

KILBORN (SASKATCHEWAN) LTD.

ESTIMATE DETAILS

PAGE 10
RUN : 30 MAR 84
TIME: 14:51

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

RUN NO. P08

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MINHS	RT	TOTAL LABOR	--- H.O. MATERIAL --- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 322 - MILL EFFLUENT TREATMENT												
4260	1	CLARIFIER THICKENER (2 REQ'D) 10000MM DIA.	2	EA				201,780	403,560		403,560	403,560
42--												
4300	5	BIN ACTIVATOR - AMMONIUM SULPHATE BIN	1	LS					1,603,560		1,603,560	1,603,560*
4300	6	DISCHARGE CHUTE - AMMON. SULPHATE BIN ACTIVATOR	1	LS				28,980	28,980		28,980	28,980
4300								2,000	2,000		2,000	2,000
4430	1	AMMONIUM SULPHATE BUCKET ELEVATOR	1	LS				30,980	30,980		30,980	30,980*
4430	2	MOTOR - 15HP	1	LS				14,400	14,400		14,400	14,400
4430								820	820		820	820
4440	1	BRIDGE CRANE - 2.5 TONNE X 30M SPAN (FACHUCA AREA)	1	LS				15,220	15,220		15,220	15,220*
4440	5	BRIDGE CRANE - 2.5 TONNE X 18M SPAN	1	LS				113,400	113,400		113,400	113,400
4440								61,400	61,400		61,400	61,400
4440								174,800	174,800		174,800	174,800*
44--								190,020	190,020		190,020	190,020*

NILBORN (SASWATCHEMAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 11

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MMPS	RT	TOTAL LABOR	--- H.O. MATERIAL --- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 372 - MILL EFFLUENT TREATMENT</u>												
4530	1	COOLING TOWER	1	LS					20,000		20,000	20,000
4610	1	VACUUM PUMPS	2	EA				36,100.00	72,200		72,200	72,200
4610	2	MOTOR - 125HP-1200RPM	2	EA				8,700.00	17,400		17,400	17,400
4610	3	LOW PRESS. AIR COMPRES- SOR - 500CH/H - 140KPA C/W RECV'R & SILENCER	1	LS					20,760		20,760	20,760
4610	4	MOTOR - 40HP	1	LS					2,200		2,200	2,200
4610	5	AIR COMPRESSOR - PROCESS AIR - 1700CH/H, 410KPA	1	LS					58,230		58,230	58,230
4610												
4630	1	CLARIFIER THICKENER NO.1 U/F DIAPHRAGM PUMP	1	LS					170,790		170,790	170,790*
4630	5	DRUM FILTER FEED PUMPS 75MM X 50MM	2	EA				2,540.00	5,080		5,080	5,080
4630	10	WASTE SLUDGE PUMP 75MM X 50MM	2	EA				2,540.00	5,080		5,080	5,080

KILBURN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

WUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 13

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MATERIALS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT	CSF	TOTAL	-- FIELD MATERIAL -- UNIT	CSF	TOTAL MATERIAL	TOTAL COST
<u>AREA 322 - MILL EFFLUENT TREATMENT</u>														
4440	1	AFFINATE TREATMENT SUMP PUMP - 75MM	1	LS						4,270			4,270	4,270
4440	5	TAILINGS NEUTRALIZATION AREA SUMP PUMP- 75MM	1	LS						4,270			4,270	4,270
4440										8,540			8,540	8,540
4450	1	COOLING WATER PUMP 100MM X 75MM	1	LS						2,585			2,585	2,585
4450	2	MOTOR - 30HP	1	LS						1,300			1,300	1,300
4450	3	TAILINGS SEEPAGE AND RUNOFF PUMPS 100MM X 75MM	2	EA				2,585.00		5,170			5,170	5,170
4450	4	MOTORS - 50HP	2	EA				2,900.00		5,800			5,800	5,800
4450	7	TAILINGS SEEPAGE AND RUNOFF PUMPS 100MM X 75MM	2	EA				2,565.00		5,170			5,170	5,170
4450	8	MOTORS - 75HP	2	EA				4,300.00		8,600			8,600	8,600
4450										28,625			28,625	28,625
44--										668,825			668,825	668,825

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

PAGE 14
RUN : 30 MAR 84
TIME: 14:51

RUN NO. P08

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	TOTAL MHRS RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
4810	5	AMMONIUM SULPHATE STORAGE BIN 600 TONNE 7000MM DIA X 14000MM	14650	KG					2.80	41,020		41,020	41,020
4820	1	JUNCTION BOX (PACHUCA FEED) 2000MM DIA. X 2500MM	900	KG					4.70	4,230		4,230	4,230
4820	2	RUBBER LINING - JUNCTION BOX	18	SM					170.00	3,060		3,060	3,060
4820	3	TAILINGS SEEPAGE AND RUNOFF TANK 10000MM DIA. X 12000MM	24200	KG					2.80	67,760		67,760	67,760
4820	5	NEUTRALIZATION PACHUCAS (4 REQ'D) 4000MM DIA. X 8000MM	32130	KG					2.80	89,964		89,964	89,964
4820	6	RUBBER LINING - PACHUCAS	365	SM					170.00	62,050		62,050	62,050
4820	10	FLASH MIX TANK 2000MM DIA X 2000MM	1055	KG					4.70	4,959		4,959	4,959
4820	11	AGITATOR	1	LS						6,725		6,725	6,725
4820	15	DRUM FILTER FEED SURGE TANK 3500MM DIA. X 3500MM	3280	KG					4.70	15,416		15,416	15,416

AREA 322 - MILL EFFLUENT TREATMENT

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 15

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 322 - MILL EFFLUENT TREATMENT</u>													
4820	20	SPLITTER BOX - DRUM FILTER FEED	1	LS					4,000		4,000	4,000	4,000
4820	30	FILTRATE TANK 3000MM DIA. X 3000MM	2396	KG				4.70	11,261		11,261	11,261	11,261
4820	35	WASTE SLUDGE PUMP BOX 1000MM X 1000MM X 1000MM	350	KG				4.70	1,645		1,645	1,645	1,645
4820	40	PRECIPITATION TANKS (4 - REQ'D) 4500MM DIA. X 4500MM	26760	KG				2.80	80,528		80,528	80,528	80,528
4820	41	AGITATOR	4	EA				15,715.00	62,860		62,860	62,860	62,860
4820	42	MOTOR - 20HP	4	EA				900.00	3,600		3,600	3,600	3,600
4820	43	EPOXY LINING - PRECIP. TANKS	13	SM	4	52	50		2,600	200.00	2,600	2,600	5,200
4820	45	FLASH MIX TANK 2000MM DIA X 2000MM	1055	KG				4.70	4,959		4,959	4,959	4,959
4820	46	AGITATOR	1	LS					6,725		6,725	6,725	6,725
4820	50	SAND FILTER PUMP BOX 1500MM DIA. X 1500MM	380	KG				4.70	1,786		1,786	1,786	1,786
4820	55	TAILINGS NEUTRALIZATION TANKS (2 REQ'D) 6000MM DIA X 8500MM	33900	KG				2.80	94,920		94,920	94,920	94,920

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 16

RUN : 30 MAR 84

TIME: 14:51

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
AREA 322 - MILL EFFLUENT TREATMENT															
4820	56	AGITATORS - RUBBER COVR'D	2	EA						28,550.00	57,100			57,100	57,100
4820	57	MOTORS - 30HP	2	EA						1,300.00	2,600			2,600	2,600
4820	58	RUBBER LINING - TAILINGS NEUTRALIZATION TANKS	386	SM	2.69	1,038	50		51,917			135.00	52,110	52,110	104,027
4820	60	TAILINGS SURGE TANK (4 REQ'D) 11000MM DIA X 11000MM	87970	KG						2.80	246,316			246,316	246,316
4820	61	AGITATORS- RUBBER COVR'D	4	EA						51,870.00	207,480			207,480	207,480
4820	62	MOTORS - 75HP	4	EA						4,300.00	17,200			17,200	17,200
4820	63	RUBBER LINING - TAILINGS SURGE TANKS	1723	SM	2.68	4,618	50		230,882			135.00	232,605	232,605	463,487
4820	65	BACKWASH TANK 4000MM DIA. X 4000MM	9240	KG						4.70	43,428			43,428	43,428
4820	70	PH ADJUSTMENT TANK 4000MM DIA. X 4000MM	9240	KG						4.70	43,428			43,428	43,428
4820						5,708			285,399		1,143,999		287,315	1,431,314	1,715,713*
4850	1	LAUNDER - DIAPHRAGM PUMP DISCHARGE	1	LS							2,000			2,000	2,000

790,270

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

WUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

PAGE 18

RUN : 30 MAR 84

TIME: 14:51

RUN NO. P08

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
AREA 322 - MILL EFFLUENT TREATMENT													
8000	1	CREDIT FROM LIME CIRCUIT (323) OF 97.7%	1	LS		14,776	50	738,800		945,378		1,195,866	1,934,686
8000	2	CREDIT FROM BARIUM CHLORIDE AREA (324) OF 64.3%	1	LS		2,074	50	103,700		114,404		125,260	228,980
8000	3	CREDIT FROM FLOCCULANT AREA (325) OF 65.7%	1	LS		1,902	50	95,100		107,934		121,008	216,108
8000	4	CREDIT FROM NITRIC ACID AREA (326) OF 50.0%	1	LS		2,642	50	132,100		161,079		190,469	322,569
6000						21,394		1,069,700		1,328,795		1,632,643	2,702,343*
AREA	322	TOTAL				127,020		6,350,999		7,882,299		10,690,482	17,041,481*

KILBORN (SASHATCHEMAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 19

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MHRS	RH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 323 - LIME CIRCUIT</u>												
2000	1	BUILDING - INCLUDES EQUIPMENT SUPPORTS & BUILDING SERVICES	8437	CM	1	8,437	50	421,850	50.00	421,850	421,850	843,700
4160	1	LIME SLAKER C/M JHP MIXER DRIVE & JHP CLASS- IFIER DRIVE	2	EA				94,400.00		188,800	188,800	188,800
4240	1	DUST COLLECTOR (LINE SILO)	2	EA				3,000.00		6,000	6,000	6,000
4300	1	BIN ACTIVATOR - LINE SILO	4	EA				11,150.00		44,600	44,600	44,600
4300	2	DISCHARGE CHUTE	4	EA				2,000.00		8,000	8,000	8,000
4300										52,600	52,600	52,600*
4420	5	SCREW CONVEYOR - LINE SILO DISCHARGE 150MM DIA X 7M LONG	2	EA				7,450.00		14,900	14,900	14,900
4630	1	LIME PUMPS - 50MM X 38MM	2	EA				6,200.00		12,400	12,400	12,400
4630	5	LIME SLURRY FEED PUMPS 50MM X 38MM	2	EA				6,200.00		12,400	12,400	12,400
4630										24,800	24,800	24,800*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. F08

PAGE 26

RUN : 30 MAR 84

TIME: 14:51

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	TOTAL LABOR	--- H.O. MATERIAL --- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 323 - LINE CIRCUIT													
4640	1	LINE AREA SUMP PUMP 50MM	1	LS						3,775		3,775	3,775
46--													
4810	1	LINE SILO - 600 TONNE EA 7000MM DIA X 20000MM (2 REQ'D)	49830	KG					2.80	139,524		139,524	139,524
										28,575		28,575	28,575*
4820	1	LINE PUMP BOX 1000MM X 1000MM X 1000MM	350	KG					4.70	1,645		1,645	1,645
4820	5	LINE SLURRY TANKS (2 REQ'D) 6000MM DIA. X 6000MM	21800	KG					2.80	61,040		61,040	61,040
4820	6	AGITATOR	2	EA				25,050.00		50,100		50,100	50,100
4820	7	MOTORS - 30HP	2	EA				1,300.00		2,600		2,600	2,600
4820										115,385		115,385	115,385*
48--										254,909		254,909	254,909*
4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS							54,580	54,580	54,580

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUFP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

PAGE 21
RUN : 30 MAR 84
TIME: 14:51

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	-- FIELD MATERIAL -- UNT CST	TOTAL MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
AREA 323 - LINE CIRCUIT															
4920	1	MECHANICAL INSTALLATION 27% OF H.O. MATERIAL	1	LS		2,947	50		147,350						147,350
49--						2,947			147,350				54,580	54,580	201,930*
4---						2,947			147,350		545,784		54,580	600,364	747,714*
5000	1	PROCESS PIPING 20% OF INSTALLED MECH.	1	LS		1,795	50		89,750				59,800	59,800	149,550
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS		1,496	50		74,800				74,750	74,750	149,550
7000	1	INSTRUMENTATION 12% OF INSTALLED MECH.	1	LS		449	50		22,450				67,275	67,275	89,725
8000	1	CREDIT TO MINERWATER TREATMENT AREA (321) OF 2.3%	-1	LS		-348	50		-17,400		-22,256		-5,897	-28,153	-45,553
8000	2	CREDIT TO MILL EFFLUENT TREATMENT AREA (322) OF 97.7%	-1	LS		-14,776	50		-738,800		-945,378		-250,508	-1,195,886	-1,934,666
8000						-15,124			-756,200		-967,634		-256,405	-1,224,039	-1,990,239*
AREA	323	TOTAL									-0			-0	-0*

KILBORN (SASATCHENNA) LTD.

PROJECT: 5239-15

MUP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 22
RUN : 30 MAR 88
TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL HOURS	MM	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 324 - BARIUM CHLORIDE</u>													
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	2318	CM	1	2,818	50	140,900	50.00	140,900		140,900	281,800
4620	1	FAN - VENTILATION (BARIUM CHLORIDE HOPPER)											
			1	LS						770		770	770
4630	20	BARIUM CHLORIDE TRANSFER PUMP - 100MM X 75MM											
			1	LS						2,890		2,890	2,890
4630	25	BARIUM CHLORIDE METERING PUMPS - 15MM X 13MM											
			2	EA					1,770.00	3,540		3,540	3,540
4630													
46--													
4820	20	BARIUM CHLORIDE MIXING TANK - 3600MM DIA X 3000MM	2396	KG									
									4.70	11,261		11,261	11,261
4820	21	MIXER - BARIUM CHLORIDE TANK											
			1	LS						5,300		5,300	5,300
4820	22	HOPPER - BARIUM CHLORIDE FEED											
			1	LS						2,000		2,000	2,000

KILBURN (SASATCHEWAN) LTD.

PROJECT: S239-15

RUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P09

PAGE 23

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
AREA 324 - BARIUM CHLORIDE														
4820	25	BARIUM CHLORIDE HOLDING TANK - 3000MM DIA X 3000MM	2396	16					4.70	11,261		11,261		11,261
4820										29,822		29,822		29,822
4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS		163	50	8,150			3,700	3,700		3,700
4920	1	MECHANICAL INSTALLATION 22% OF H.O. MATERIAL	1	LS		163	50	8,150						8,150
49--						163		8,150			3,700	3,700		11,850
4---						163		8,150		37,022	3,700	40,722		48,872
5000	1	PROCESS PIPING 20% OF INSTALLED MECH.	1	LS		117	50	5,850			3,925	3,925		9,775
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS		98	50	4,900			4,875	4,875		9,775
7000	1	INSTRUMENTATION 12% OF INSTALLED MECH.	1	LS		29	50	1,450			4,415	4,415		5,865

KILBURN (SASWATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 24
RUN : 30 MAR 84
TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MINS	PH KT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL COST
8000	1	CREDIT TO MINERWATER TREATMENT AREA (321) OF 35.7%	-1	LS		-1,151	50	-57,550	-63,518		-6,039	-69,557	-127,107
8000	2	CREDIT TO WLL EFFLUENT TREATMENT AREA (322) OF 64.3%	-1	LS		-2,074	50	-103,700	-114,404		-10,876	-125,280	-229,980
8000						-3,225		-161,250	-177,922		-16,915	-194,837	-356,067
AREA	324	TOTAL							0		0	0	0

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 25
RUN : 30 MAR 84
TIME: 14:51

CLS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	RT	LABOR	--- H.O. MATERIAL --- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 325 - FLOCCULANT													
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	2415	CM	1	2,415	50	120,750	50.00	120,750		120,750	241,500
4630	40	FLOCCULANT TRANSFER PUMP 50MM X 50MM	1	LS						3,100		3,100	3,100
4630	45	FLOCCULANT METERING PUMP 25MM X 25MM	2	EA					1,770.00	3,540		3,540	3,540
4630										6,640		6,640	6,640
4820	40	FLOCCULANT MIXING TANK 3000MM DIA X 3000MM	2396	KG					4.70	11,261		11,261	11,261
4820	41	MIXER - FLOCCULANT TANK	1	LS						5,300		5,300	5,300
4820	42	ASPIRATOR	1	LS						200		200	200
4820	45	FLOCCULANT STOCK TANK 4500MM DIA X 4500MM	7190	KG					2.80	20,132		20,132	20,132
4820										36,893		36,893	36,893

KILBORN (SASATCHEMAN) LTD.

PROJECT: S239-15

NUTF WASTE MANAGEMENT COST STUDY MODEL C

CLASS ITEM DESCRIPTION

QUAN UN

UNIT

TOTAL MHRS

MH RT

TOTAL

LABOR

-- H.O. MATERIAL --

UNIT CST

TOTAL

- FIELD

UNIT CST

TOTAL

MATERIAL

TOTAL

TOTAL

MAT'L

TOTAL

COST

AREA 325 - FLOCCULANT

4910 1 FIELD MATERIAL - 10% OF H.O. MATERIAL 1 LS

4920 1 MECHANICAL INSTALLATION 2% OF H.O. MATERIAL 1 LS

49--

4---

5000 1 PROCESS PIPING 20% OF INSTALLED MECH. 1 LS

6000 1 ELECTRICAL 20% OF INSTALLED MECH. 1 LS

7000 1 INSTRUMENTATION 1% OF INSTALLED MECH. 1 LS

8000 1 CREDIT TO MINERWATER TREATMENT AREA (321) OF 34.3% -1 LS

8000 2 CREDIT TO MILL EFFLUENT TREATMENT AREA (322) OF 65.7% -1 LS

5000

ESTIMATE DETAILS

RUN NO. P08

PAGE 26

RUN : 30 MAR 84

TIME: 14:51

4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS	192	50	9,600			4,350	4,350	4,350	
4920	1	MECHANICAL INSTALLATION 2% OF H.O. MATERIAL	1	LS	192		9,600			4,350	4,350	4,350	
49--					192		9,600			4,350	4,350	4,350	
4---					192		9,600			4,350	4,350	4,350	
5000	1	PROCESS PIPING 20% OF INSTALLED MECH.	1	LS	138	50	6,900		43,533	4,600	4,600	11,500	
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS	115	50	5,750			5,750	5,750	11,500	
7000	1	INSTRUMENTATION 1% OF INSTALLED MECH.	1	LS	34	50	1,700			5,200	5,200	6,900	
8000	1	CREDIT TO MINERWATER TREATMENT AREA (321) OF 34.3%	-1	LS	-992	50	-49,600		-56,349	-6,826	-63,175	-112,775	
8000	2	CREDIT TO MILL EFFLUENT TREATMENT AREA (322) OF 65.7%	-1	LS	-1,502	50	-75,100		-197,924	-17,074	-121,008	-216,108	
5000					-2,894		-144,700		-164,283	-19,900	-184,183	-328,883	

KILBORN (SASATCHEN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

CLASS ITEM DESCRIPTION

AREA 325 - FLOCCULANT

ESTIMATE DETAILS

RUN NO. PUB

UNIT
MURS
MURS
MURS

TOTAL
MURS
MURS
MURS

TOTAL
LABOR
LABOR

TOTAL
MATERIAL -
MATERIAL -

TOTAL
MATERIAL
COST

AREA 325 TOTAL

0

0

04

PAGE 27

RUN : 30 MAR 84

TIME: 14:51

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 28

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
AREA 326 - NITRIC ACID														
2000	1	BUILDING - INCLUDING EQUIPMENT SUPPORTS & BUILDING SERVICES	3867	CM	I	3,867	50		193,350	50.00	193,350		193,350	386,700
4310	1	NITRIC ACID IN-LINE MIXER (ST/STEEL)	1	LS							1,800		1,800	1,800
4630	30	NITRIC ACID TRANSFER PUMP - 75MM X 38MM (STAINLESS/STL)	1	LS							3,520		3,520	3,520
4630	35	NITRIC ACID DISTRIBUTION PUMP 100MM X 75MM (STAINLESS/STL)	1	LS							4,840		4,840	4,840
4630														
4640	10	NITRIC ACID AREA SUMP PUMP - 50MM (STAINLESS/STL)	1	LS							8,360		8,360	8,360*
4640											5,700		5,700	5,700
46--														
4820	30	NITRIC ACID STOCK TANK 4000MM DIA X 4000MM (STAINLESS STL)	5435	K6						5.77	14,060		14,060	14,060*
											31,360		31,360	31,360

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 29

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MHRS	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
AREA 326 - NITRIC ACID													
4820	35	NITRIC ACID HOLDING TANK 6500MM DIA X 6500MM (STAINLESS STL)	14140	KG				5.77	81,588			81,588	81,588
4820			19575	KG				5.77	112,948			112,948	112,948*
4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS							12,880	12,880	12,880
4920	1	FIELD INSTALLATION 22% OF H.O. MATERIAL	1	LS	567	50	28,350						28,350
49--					567		28,350				12,880	12,880	41,230*
4---					567		28,350		128,808		12,880	141,688	170,038*
5000	1	PROCESS PIPING 20% OF INSTALLED MECH.	1	LS	408	50	20,400				13,600	13,600	34,000
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS	340	50	17,000				17,000	17,000	34,000
7000	1	INSTRUMENTATION 12% OF INSTALLED MECH.	1	LS	102	50	5,100				15,300	15,300	20,400
8000	1	CREDIT TO MINERWATER TREATMENT AREA (321) OF 50.0%	-1	LS	-2,642	50	-132,100		-161,079		-29,390	-190,469	-322,569

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 30

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	MHRS	TOTAL MHRS	MH	RT	TOTAL LABOR	-- H.D. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 326 - NITRIC ACID</u>																
8000	2	CREDIT TO MILL EFFLUENT TREATMENT AREA (322) OF 50.0%	-1	LS			-2,642	50		-132,100		-161,079	-29,390		-190,469	-322,569
8000							-5,284			-264,200		-322,158	-58,780		-380,938	-645,138*
AREA	326	TOTAL										-0			-0	-0*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

PAGE 31

RUN : 30 MAR 84

TIME: 14:51

RUN NO. P08

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 331 - TAILINGS LINE</u>															
1800	1	TAILINGS LINE - 100MM DIA. SCH. 80 C.S.LINES (2 REQ'D)	4860	M	.309	1,502	50		75,087	58.20	282,852	6.58	31,979	314,831	389,918
1800	2	TAILINGS LINE - 300MM DIA. SCH 40 C. STL.	2430	M	.782	1,900	50		95,013	189.30	459,999	16.46	39,998	499,997	595,010
1800	3	TAILINGS LINE - 150MM DIA. SCH. 40 C. STL.	1670	M	.311	519	50		25,968	64.70	108,049		11,005	119,054	145,023
1800	4	TAILINGS LINE - CONCRETE UTILIDOR C/W CORR. METAL COVER	2430	M	1.95	4,741	50		237,046			97.94	237,994	237,994	475,041
1800	5	TAILINGS LINE FILL MATERIAL	5625	CM								4.40	24,750	24,750	24,750
1800						8,662			433,115		850,900		345,726	1,196,626	1,629,741*
1900	1	CENTRAL SUMP C/W LINER	1	LS							3,500		3,500	7,000	7,000
1---						8,662			433,115		854,400		349,226	1,203,626	1,636,741*
7000	1	INSTRUMENTATION -5%	1	LS		409	50		20,450				61,350	61,350	81,800
AREA	331	TOTAL				9,071			453,565		854,400		410,576	1,264,976	1,718,541*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 32

RUN : 30 MAR 84

TIME: 14:51

CLSS	ITM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	MATERIAL TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>														
1900	1	PERMANENT ROADWAYS CLEARING	26000	SM							1.64	42,640	42,640	42,640
1900	2	PERMANENT ROADWAYS FILL MATERIAL	32500	CM							4.40	143,000	143,000	143,000
1900	3	PERMANENT ROADWAYS- GRANULAR SURFACE	1500	CM							4.92	7,380	7,380	7,380
1900	5	POWER SUPPLY LINE	1670	M	.072	120	50	6,012			7.76	12,993	12,993	19,005
1900	10	PUMPHOUSE	36	CM	1.11	40	50	1,998			55.55	2,000	2,000	3,998
1900						160		8,010				208,012	208,012	216,022*
1910	15	TAILINGS POND MOBILIZE & DEMOBILIZE	1	LS								1,200,000	1,200,000	1,200,000
1910	16	TAILINGS POND - CLEARING & GRUBBING	63	HA							15,000	945,000	945,000	945,000
1910	17	TAILINGS POND - EXCAVATE	1200000	CM							2.70	3,240,000	3,240,000	3,240,000
1910	18	TAILINGS POND - BENTONITE SEAL	9000	TN							240.92	2,168,280	2,168,280	2,168,280

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 34

RUN : 30 MAR 84
TIME: 14:51

CLS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL MAT'L	TOTAL COST
<u>AREA 332 - TAILINGS STORAGE BASIN</u>													
1910	27	TAILINGS POND - SUMP ENCLOSURE	1	LS							10,000	10,000	10,000
1910	28	TAILINGS POND - VALVE HOUSE	1	LS							10,000	10,000	10,000
1910						10,500		525,000			11,196,579	11,196,579	11,721,579*
19--						10,660		533,010			11,404,592	11,404,592	11,937,602*
AREA	332	TOTAL				10,660		533,010			11,404,592	11,404,592	11,937,602*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 8239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 35

RUN : 30 MAR 84

TIME: 14:51

CLSS	ITH	DESCRIPTION	QUAN	UN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD MATERIAL - UNT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 334 - MONITORING</u>														
1900	1	MONITORING PONDS - CUT MATERIAL	59070	CM							2.70	159,489	159,489	159,489
1900	2	MONITORING PONDS - FILL & PLACEMENT MATERIAL	57137	CM					1.70	97,133		97,133		97,133
1900	3	MONITORING PONDS CLEARING	2	HA					16,375	32,750		32,750		32,750
1900	4	MONITORING PONDS- SAND FILTER BLANKET	3410	CM					2.20	7,502		7,502		7,502
1900	5	MONITORING PONDS - BENTONITE SEAL	40	TN					338.89	13,556		13,556		13,556
1900	6	MONITORING PONDS- 100MIL SYNTHETIC SEAL	10450	SM					20.63	215,584		215,584		215,584
1900	7	MONITORING FONDs - DRAINAGE PIPES	485	M					8.51	4,127		4,127		4,127
1900	8	MONITORING FONDs - MISC. PIPING	1	LS						173,855		173,855		173,855
1900	9	MONITORING FONDs - CONC. VALVA HOUSE, SUMPS, & INSTRUMENTATION	1	LS						70,000		70,000		70,000

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 36

RUN : 30 MAR 84

TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UNIT	TOTAL MNHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	- FIELD MATERIAL - UNIT CST	TOTAL MAT'L	TOTAL CUST
AREA 334 - MONITORING											
1900	10	MONITORING PONDS - PIEZOMETERS	5	EA					1,100	5,500	5,500
1900									779,495	779,495	779,495*
2000	1	LABORATORY BUILDING	300	SM	10	50	150,000	500.00		150,000	300,000
2000	2	CREDIT TO PRODUCTION CAPITAL COST - 70%	-1	LS	-2,100	50	-105,000			-105,000	-210,000
2000					900		45,000			45,000	90,000*
4000	1	LAB EQUIPMENT	1	LS			450,000			450,000	450,000
4000	2	CREDIT TO PRODUCTION CAPITAL COST - 70%	-1	LS			-315,000			-315,000	-315,000
4000							135,000			135,000	135,000*
4640	2	RECYCLE WATER SUMP PUMP 50MM	2	EA			5,135.00			10,270	10,270
4640	3	MOTOR - 40HP	2	EA			2,200.00			4,400	4,400
4640										14,670	14,670*
4650	5	RECYCLE WATER PUMPS 150MM X 100MM	2	EA			3,860.00			7,720	7,720

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

CLSS ITH DESCRIPTION

UNIT

TOTAL MH

LABOR

-- H.O. MATERIAL --
UNT CST TOTAL

- FIELD MATERIAL -
UNT CST TOTAL

TOTAL
MAT'L

TOTAL
COST

ESTIMATE DETAILS

RUN NO. P08

PAGE 37

RUN : 30 MAR 84

TIME: 14:51

AREA 334 - MONITORING

4650	6	MOTOR - 50HP	2	EA				2,900.00	5,800		5,800	5,800
4650												
46--												
4820	4	RECYCLE WATER PUMP BOX 2500MM DIA. X 3500MM	1700	KG				4.70	7,990		7,990	7,990
4910	1	FIELD MATERIAL - 10% OF H.O. MATERIAL	1	LS						17,100	17,100	17,100
4920	1	MECHANICAL INSTALLATION 22% OF H.O. MATERIAL	1	LS		753	50	37,650				37,650
49--						753		37,650		17,100 -	17,100	54,750*
4---						753		37,650	171,180	17,100	188,290	225,930*
5000	1	PROCESS PIPING - 20% OF INSTALLED MECH.	1	LS		542	50	27,100		18,100	18,100	45,200
6000	1	ELECTRICAL 20% OF INSTALLED MECH.	1	LS		452	50	22,600		22,600	22,600	45,200

TIME: 14:51

CLASS	ITEM	DESCRIPTION
100	100	100
200	200	200
300	300	300
400	400	400
500	500	500
600	600	600
700	700	700
800	800	800
900	900	900

AREA 334 - MONITORING

7000 1 INSTRUMENTATION
12% OF INSTALLED MECH.

157

136 50

6,800

UNIT	HRS
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

MILITARY AND NAVAL

TOTAL	HH
MNHR	RT

TOTAL
LABOR

UNIT	CST	TOTAL
-- H.O. MATERIAL --		

UNIT COST	- FIELD MATERIAL -	TOTAL
100	100	100
200	200	200
300	300	300
400	400	400
500	500	500
600	600	600
700	700	700
800	800	800
900	900	900
1000	1000	1000
1100	1100	1100
1200	1200	1200
1300	1300	1300
1400	1400	1400
1500	1500	1500
1600	1600	1600
1700	1700	1700
1800	1800	1800
1900	1900	1900
2000	2000	2000
2100	2100	2100
2200	2200	2200
2300	2300	2300
2400	2400	2400
2500	2500	2500
2600	2600	2600
2700	2700	2700
2800	2800	2800
2900	2900	2900
3000	3000	3000
3100	3100	3100
3200	3200	3200
3300	3300	3300
3400	3400	3400
3500	3500	3500
3600	3600	3600
3700	3700	3700
3800	3800	3800
3900	3900	3900
4000	4000	4000
4100	4100	4100
4200	4200	4200
4300	4300	4300
4400	4400	4400
4500	4500	4500
4600	4600	4600
4700	4700	4700
4800	4800	4800
4900	4900	4900
5000	5000	5000
5100	5100	5100
5200	5200	5200
5300	5300	5300
5400	5400	5400
5500	5500	5500
5600	5600	5600
5700	5700	5700
5800	5800	5800
5900	5900	5900
6000	6000	6000
6100	6100	6100
6200	6200	6200
6300	6300	6300
6400	6400	6400
6500	6500	6500
6600	6600	6600
6700	6700	6700
6800	6800	6800
6900	6900	6900
7000	7000	7000
7100	7100	7100
7200	7200	7200
7300	7300	7300
7400	7400	7400
7500	7500	7500
7600	7600	7600
7700	7700	7700
7800	7800	7800
7900	7900	7900
8000	8000	8000
8100	8100	8100
8200	8200	8200
8300	8300	8300
8400	8400	8400
8500	8500	8500
8600	8600	8600
8700	8700	8700
8800	8800	8800
8900	8900	8900
9000	9000	9000
9100	9100	9100
9200	9200	9200
9300	9300	9300
9400	9400	9400
9500	9500	9500
9600	9600	9600
9700	9700	9700
9800	9800	9800
9900	9900	9900
10000	10000	10000

TOTAL

TOTAL

AREA 334 TOTAL

2,783

139, 150

216.180

857,595

1,073,775

1,212,925#

KILBORN (SASKATCHEWAN) LTD.

PROJECT: 5239-15

MUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

PAGE 39

RUN : 30 MAR 84

TIME: 14:51

CLS	ITM	DESCRIPTION	QUN	UN	UNIT	TOTAL MHRS	MH	RT	TOTAL LABOR	-- H.O. MATERIAL -- UNIT CST	TOTAL	- FIELD MATERIAL - UNIT CST	TOTAL	TOTAL MAT'L	TOTAL COST
<u>AREA 900 - CONST. INDIRECTS, E.P.C.M., & CONTINGENCY</u>															
9100	1	CONSTRUCTION INDIRECTS	1	LS		28,400	50		1,420,000				1,420,100	1,420,100	2,840,100
9200	1	ENGINEERING, PROCUREMENT AND CONSTRUCTION MANAGEMENT	1	LS							4,260,100			4,260,100	4,260,100
9300	1	SPARE PARTS - 5% OF H.O. MATERIAL	1	LS							731,150			731,150	731,150
9900	1	CONTINGENCY	1	LS		20,103	50		1,005,150		1,535,420		1,792,615	3,328,035	4,333,185
9---						48,503			2,425,150		6,526,670		3,212,715	9,739,385	12,164,535*
AREA	900	TOTAL				48,503			2,425,150		6,526,670		3,212,715	9,739,385	12,164,535*

KILBORN (SASKATCHEWAN) LTD.

PROJECT: S239-15

NUTP WASTE MANAGEMENT COST STUDY MODEL C

ESTIMATE DETAILS

RUN NO. P08

RUN : 30 MAR 84
TIME: 14:51

CLASS	ITEM	DESCRIPTION	QUAN	UN	UNIT	TOTAL MHRS	MH RT	TOTAL LABOR	-- H.O. MATERIAL -- UNT CST	TOTAL	- FIELD UNT CST	MATERIAL - TOTAL	TOTAL MAT'L	TOTAL COST
TOTAL	DIRECTS					221,137		11,056,829		16,889,595		19,718,768	36,608,363	47,665,192*
TOTAL	DIRECTS AND INDIRECTS					221,137		11,056,829		16,889,595		19,718,768	36,608,363	47,665,192*
CONTINGENCY														0*
PROJECT	TOTAL					221,137		11,056,829		16,889,595		19,718,768	36,608,363	47,665,192*

POOR

QUALITY

ORIGINAL